SITE DEVELOPMENT PLANS FOR:

BROOK RUN DOG PARK **DESIGN DEVELOPMENT**

4770 N. PEACHTREE RD. **DUNWOODY, DEKALB COUNTY, GEORGIA 30338** L.L. 354, 18TH DISTRICT, ZONED: R-85

Sheet List Table

COVER

SURVEY

C-0 DEMOLITION PLAN

SITE & PAVING PLAN GRADING & DRAINAGE PLAN

C-3 **UTILITIES PLAN**

C-3.1 STORM DRAINAGE PROFILES

INITIAL EROSION & SEDIMENT CONTROL PLAN C-4 INTERMEDIATE EROSION & SEDIMENT CONTROL PLAN C-4.1

FINAL EROSION & SEDIMENT CONTROL PLAN C-4.2

C-4.3 **EROSION CONTROL NOTES**

PAVING DETAILS C-5

CONSTRUCTION DETAILS C-6

UTILITIES DETAILS C-7

EROSION CONTROL DETAILS **EROSION CONTROL DETAILS** C-8.1

LANDSCAPE PLAN L-1

ARCHITECTURAL COVER

A-1.1 FLOOR PLAN

ELEVATIONS AND DETAILS

SCHEDULE OF INSPECTIONS HVAC NOTES, ETC. M-1

M-2 **HVAC FLOOR PLAN**


ELECTRICAL LEGEND, SYMBOLS, AND GENERAL NOTES E-0.1

ELECTRICAL POWER PLAN E-1.1

ELECTRICAL SPECIFICATIONS E-2.1


PLUMBING NOTES P-1

PLUMBING PLANS



VICINITY MAP NOT TO SCALE

SITE DISTURBED AREA = 1.6 AC



THIS SITE IS NOT LOCATED WITHIN A ZONE A, AE, OR SHADED ZONE X AS DEFINED BY FIRM COMMUNITY PANEL NUMBER 13121C FOR UNINCORPORATED DEKALB COUNTY, GEORGIA.



PREPARED BY:



Foresite Group, Inc. 5185 Peachtree Pkwv. Suite 240 Norcross, GA 30092

o | 770.368.1399 **f** | 770.368.1944 w | www.fg-inc.net

24 HR CONTACT: **BRENT WALKER** (678) 382-6700

ISSUED: AUGUST 9, 2013 487.001

CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY UPON START OF CONSTRUCTION IN ORDER FOR ENGINEER TO SCHEDULE THE INITIAL 7 DAY EROSION CONTROL INSPECTION. THE CONTRACTOR SHALL VERIFY THAT ALL EXISTING INITIAL BMP'S ARE INSTALLED PROPERLY, ALL COMPENSATION FOR DESIGN ENGINEER'S REINSPECTION TO VERIFY THAT THE INITIAL BMP'S ARE PROPERLY INSTALLED WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.

PROJECT DIRECTORY

OWNER/DEVELOPER CITY OF DUNWOODY PARKS & RECREATION 41 PERIMETER CENTER EAST, SUITE 250 DUNWOODY, GA 30346 (678) 382-6700 CONTACT: MR. BRENT WALKER LANDSCAPE ARCHITECT/CIVIL ENGINEER **FORESITE GROUP, INC.** 5185 PEACHTREE PKWY., SUITE 240 NORCROSS, GA 30092 (770) 368-1399 CONTACT: JASON WECKERLY ARCHITECT


ATLANTA, GA 30360 (404) 803-3869 CONTACT: MR. CHRIS KACENA SURVEYOR GEOSURVEY, LTD. 1660 BARNES MILL RD. MARIETTA, GA 30062 (77) 795-9900


KACENA DESIGN, LLC 2944 RIDGELOCK CT.

UTILITY PROVIDERS

WATER & SEWER SERVICE PROVIDER **DEKALB DEPT. OF WATERSHED** MANAGMENT 1580 ROADHAVEN DRIVE STONE MOUNTAIN, GA 30083 (770) 621-7200 CONTACT: MR. RUDOLPH A. CHEN

ELECTRICAL SERVICE PROVIDER GEORGIA POWER 1841 CHAMBLEE TUCKER RD. SUITE 1-1A CHAMBLEE, GA 30341 (770) 216-1313 CONTACT: MR. J.C. PORCH







SIGNATURE OF ENGINEER	DATE



f | 770,368,1944

EVELOPER:
ONTACT:
enno:

DESIGN DEVELOPMENT



REVISIONS	DATE


PROJECT MANAGER:	JVW
DRAWING BY:	NJP
JURISDICTION:	DUNWOODY, GA
DATE:	9 AUGUST 2013
SCALE:	AS SHOWN
TITLE:	


COVER


SHEET NUMBER


COMMENTS: NOT RELEASED FOR CONSTRUCTION


JOB/FILE NUMBER: 487.001




















EROSION CONTROL NOTES:

- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN QUALIFIED PROFESSIONAL ADVICE WHEN QUESTIONS ARISE ON ON TRACTOR SHARE OF THE CONTRACT OF THE CONTRACT OF THE CONTRACT: JASON WECKERLY (770) 388-1339. ONTRACTOR SHALL INFORM REGINEER WHEN CONSTRUCTION BEGINS.
- THE INSTALLATION OF EROSION CONTROL MEASURES AND PRACTICES SHALL TAKE PLACE PRIOR TO OR CONCURRENT WITH LL LAND DISTURBING ACTIVITIES THROUGHOUT THE ENTIRE PROJECT.
- ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR
- PROSION AND SEDIMENT CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE PPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTRO EASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
- THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION CONTROL MEASURES ND PRACTICES PRIOR TO, OR CONCURRENT WITH, ALL LAND DISTURBING ACTIVITIES THROUGHOUT THE ENTIRE PROJECT.
- SEDIMENT STORAGE INDICATORS MUST BE INSTALLED IN SEDIMENT STORAGE STRUCTURES, INDICATING THE 1/3 FULL
- THE CONTRACTOR SHALL REMOVE ACCUMULATED SILT WHEN THE ACCUMULATED SILT IS ONE-THIRD (1/3) FULL FOR ALL ROSION & SEDIMENT CONTROL STRUCTURES.
- MAINTENANCE OF ALL SOIL EROSION AND SEDIMENTATION CONTROL MEASURES AND PRACTICES, WHETHER TEMPORARY OR ERMANENT, SHALL BE AT ALL TIMES THE RESPONSIBILITY OF THE PROPERTY OWNER.
- 9) A 25-FOOT UNDISTURBED BUFFER IS TO BE MAINTAINED ADJACENT TO ALL STREAMS.
- D) DETENTION POND, DETENTION OUTLET STRUCTURES AND TEMPORARY SEDIMENT POND FEATURES ARE TO BE ONSTRUCTED AND FULLY OPERATIONAL PRIOR TO ANY OTHER CONSTRUCTION.
- 1) ALL FILL SLOPES SHALL HAVE SILT FENCE PLACED AT THE SLOPE'S TOE.
- CONCENTRATED FLOW AREAS AND ALL SLOPES STEEPER THAN 2.5:1 WITH A HEIGHT OF TEN FEET OR GREATER SHALL STABILIZED WITH THE APPROPRIATE EROSION CONTROL MATTING.
- 13) THE PROFESSIONAL WHO SEALS THIS PLAN CERTIFIES UNDER PENALTY OF LAW THAT THIS PLAN WAS PREPARED AFTER A SITHE PROFESSIONAL SYMMET SHEET SHEEPINSION.
- i) EROSION CONTROL DEVICES THAT ARE INSTALLED AS DIRECTED BY THE LAND DEVELOPMENT INSPECTOR BUT NOT SHOWN N THE APPROVED PLAN AND WHICH ALSO SUBSEQUENTLY FAIL, ARE THE RESPONSIBILITY OF THE CONTRACTOR.
- 15) ALL TEMPORARY AND PERMANENT SEEDING MUST BE PERFORMED AT THE APPROPRIATE SEASON. ADDITIONAL PLANTINGS WILL BE NECESSARY IF A SUFFICIENT STAND OF GRASS FAILS TO GROW.
- 6) TOPSOIL SHALL BE STOCKPILED AND USED TO DRESS FINAL GRADES.
- 7) NO PORTION OF THE SUBJECT PROPERTY LIES WITHIN A 100 YEAR FLOOD HAZARD AREA PER FIRM MAP NUMBER 13089C0016J
- 8) THE CONTRACTOR WILL CLEAN OUT ACCUMULATED SILT IN THE STORM DRAINAGE PIPES AT END OF CONSTRUCTION WHEN DISTURBED AREAS HAVE BEEN STABILIZED.
- 9) ALL LOTS WITH WET LAND OR WITHIN A DAM ZONE SHALL BE DENOTED WITH AN ASTERISK
- 20) APPROVAL OF THESE PLANS DOES NOT CONSTITUTE APPROVAL BY THE CITY OF DUNWOODY OR EPD OF ANY LAND DISTURBING ACTIVITIES WITHIN WETLAND AREAS AND/OR WHICH MAY IMPACT ENDANGERED SPECIES. IT IS THE RESPONSIBIL OF THE PROPERTY OWNER TO CONTACT THE APPROPRIATE REGULARITY AGENCY FOR APPROVAL OF ANY DISTURBANCE WH MAY HAVE THIS EFFECT.
- ALL CONSTRUCTION SHALL COMPLY WITH THE SPECIFICATIONS AND PROCEDURES DETAILED IN THE CURRENT DEVELOPMEN' EGULATIONS OF THE CITY OF DUNWOODY AND THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GA.
- 22) TWO ROWS OF GA. D.O.T. TYPE C SILT FENCE SHALL BE INSTALLED ADJACENT TO STATE WATERS AND WILL PROTECT STATE WATERS FROM ANY I AND DISTURBING ACTIVITIES
- 23) ALL SLOPES AND AREAS DISTURBED DURING CONSTRUCTION SHALL BE GRADED SMOOTH AND 4° OF TOPSOIL APPLIED. THE AREA SHALL THEN BE SEEDED, FERTILIZED, MULCHED, WATERED AND MAINTAINED UNTIL HEALTHY STAND OF PERMAMENT VEGETATION HAS BEEN ESTABLEHED FOR ALL DISTURBED AREAS. SEEDS FOR GRASSED AREAS USE THE FOLLOWINGTURES.
- 24) ALL SILT BARRIERS MUST BE PLACED AS ACCESS IS OBTAINED DURING CLEARING. NO GRADING SHALL TAKE PLACE UNTIL SILT BARRIER INSTALLATION IS COMPLETE.
- 25) SILT BARRIERS SHALL BE PLACED AS SHOWN AND/OR AS DIRECTED BY THE PROJECT ENGINEER AND/OR COUNTY
- 5) CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING EROSION CONTROL MEASURES UNTIL CONSTRUCTION IS COMPLETE ND PERMANENT VEGETATION HAS BEEN ESTABLISHED.
- 27) ALL DISTURBED AREAS SHALL BE GRASSED AS SOON AS POSSIBLE AS PER THE SEEDING SCHEDULES AND RATES.
- 8) ALL OPEN DRAINAGE SWALES MUST BE GRASSED AND RIP-RAP PLACED AS REQUIRED TO PREVENT EROSION
- A) MAXIMUM SLOPES ON CUT OR FILL SECTIONS SHALL NOT EXCEED 2 TO 1. 0) ALL FILL AREAS AND DITCH WORK ON THIS SITE SHALL BE COMPACTED TO A MINIMUM 95% STANDARD PROCTOR
- 31) ALL DRAINAGE STRUCTURES SHALL HAVE RING AND COVER ACCESS.
- 32) LENGTH OF STORM WATER OUTFALL STRUCTURE RIP-RAP SHALL BE AT LEAST 6 TIMES THE DIAMETER OF THE STORM DRAIN
- (3) WHERE APPLICABLE, EACH INDIVIDUAL LOT BUILDER SHALL BE RESPONSIBLE FOR INSTALLING AND MAINTAINING EROSION CONTROL MEASURES ON THEIR OWN LOT.
- (4) SECONDARY PERMITTEES SHALL BE RESPONSIBLE FOR RETURNING AREAS DISTURBED DURING THEIR ACTIVITIES TO THE CONDITION PRIOR TO THEIR DISTURBANCE (TO INCLUDE SEEDING, STRAW, OR OTHER PRE-EXISTING BMP CONTROLS APPLIED)
- (8) EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED IF DEEMED NECESSARY BY ON-SITE INSPECTIONS.
- (8) INSPECTIONS ARE TO BE MADE AFTER EACH RAINFALL EVENT AND SILT ACCUMULATIONS SHALL BE REMOVED FROM ANY SEDIMENT BASINS AND PLACED AT A STABLE LOCATION WHERE IT IS TO BE SEEDED AND MULCHED.
- 37) SEE EROSION CONTROL DETAIL SHEET FOR EROSION CONTROL DETAILS & SEEDING RATES AND SCHEDULES.
- IS) RED LINE COMMENTS ON WORKING SETS OF PLANS SHOULD BE MAINTAINED ON SITE FOR ANY CHANGES MADE TO EROSION CONTROL PLAN. COMMENTS SHOULD INCLUDE DATE AND JUSTIFICATION FOR CHANGES.
- 39) PRIOR TO ANY OTHER CONSTRUCTION, A STABILIZED CONSTRUCTION ENTRANCE SHALL BE INSTALLED AT EACH POINT OF ENTRY TO OR EXIT FROM THE SITE. ANY MUD, DIRT, OR ROCK TRACKED FROM THE SITE WILL BE CLEANED AS NECESSARY. DUMF
- 40) PRIOR TO COMMENCING LAND DISTURBING ACTIVITY, THE LIMITS OF DISTURBANCE SHALL BE CLEARLY AND ACCURATELY WARKED WITH STAKES, RIBBON OR OTHER APPROPRIATE MEANS. THE LOCATION AND EXTENT OF ALL AUTHORIZED LAND DISTURBANCE SHALL BE DEMARCATED FOR THE DURATION OF THE CONSTRUCTION ACTIVITY. NO LAND DISTURBANCE SHALL OCCUR OUTSIDE THE APPROVED LIMITS INDICATED ON THE APPROVED PLANS.
- 41) IMMEDIATELY AFTER THE ESTABLISHMENT OF CONSTRUCTION ENTRANCE/EXITS, ALL PERIMETER EROSION CONTROL SHALL BE INSTALLED PRIOR TO ANY OTHER CONSTRUCTION.

CERTIFICATION STATEMENT:

Know what's **below**

"I CERTIFY THAT THE PERMITTEE'S EROSION, SEDIMENTATION, AND POLLUTION CONTROL PLAN PROVIDES FOR AN APPROPRIATE AND COMPREHENSIVE SYSTEM OF BEST MANAGEMENT FRACTICES REQUIRED BY THE GEORGIA WATER QUALITY CONTROL ACT AND THE DOCUMENT "MANUAL PROPERSON ON SEDIMENT CONTROL IN CERCIFICA" (MANUAL) PUBLISHED BY THATE SOIL AND WATER CONSERVATION COMMISSION AS OF JANUARY 1 OF THE YEAR IN WHICH THE LAND-DISTURBING ACTIVITY WAS PERMITTED, PROVIDES FOR THE SAMPLING OF THE RECEIVING WATERS) OR THE SAMPLING OF THE STORM WATER AND THAT THE DESIGNED SYSTEM OF THE BEST MANAGEMENT FRACTICES AND SAMPLING METHODS IS EXPECTED TO MEET THE REQUIREMENTS CONTAINED IN THE GENERAL NPDES PERMIT NO. GAR 100001. ADDITIONALLY, I CERTIFY UNDER PENALTY OF LAW THAT THIS PLAN WAS PREPARED AFTER A SITE VISIT TO THE LOCATIONS DESCRIBED HEREIN BY MYSELF OR MY AUTHORIZED

SIGNATURE OF ENGINEER

11/4/13 DATE

GENERAL NOTES

THIS PLAN INCLUDES, AS A MINIMUM, BEST MANAGEMENT PRACTICES, INCLUDING SOUND CONSERVATION AND ENGINEERING PRACTICES TO PREVENT AND MINIMIZE EROSION AND RESULTANT SEDIMENTATION, WHICH ARE CONSISTENT WITH, AND NO LESS STRINGENT THAN, THOSE PRACTICES CONTAINED IN THE "MANULAL FOR REGISION AND SEDIMENT CONTROL IN GEORGIA" (MANULAL) PUBLISHED BY THE STATE SOIL AND WATER CONSERVATION COMMISSION AS OF JANUARY 1 OF THE YEAR IN WHICH THE LAND DISTURBING ACTIVITY WAS PERMITTED, AS WELL AS THE FOLLOWING

- STRIPPING OF VEGETATION, CUT AND FILL OPERATIONS, AND OTHER DEVELOPMENT ACTIVITIES WILL BE CONDUCTED IN A
- 2) DEVELOPMENT PLANS CONFORM TO TOPOGRAPHY AND SOIL TYPE, SO AS TO CREATE THE LOWEST PRACTICABLE EROSION POTENTIAL
- THE DISTURBED AREA AND THE DURATION OF EXPOSURE TO EROSIVE ELEMENTS WILL BE KEPT TO A PRACTICAL MINIMUM.
 WHENEVER FEASIBLE, NATURAL VEGETATION WILL BE RETAINED, PROTECTED, AND SUPPLEMENTED.
- 4) DISTURBED SOIL WILL BE STABILIZED AS QUICKLY AS PRACTICABLE
- 5) TEMPORARY VEGETATION OR MULCHING WILL BE EMPLOYED TO PROTECT EXPOSED CRITICAL AREAS DURING DEVELOPMENT AT A MINIMUM OF EVERY 7 DAYS IF THE SOIL HAS BEEN LEFT UNDISTURBED.
- PERMANENT VEGETATION AND STRUCTURAL EROSION CONTROL MEASURES WILL BE INSTALLED AS SOON AS PRACTICABLE 7) TO THE EXTENT NECESSARY, SEDIMENT IN RUN-OFF WATER WILL BE TRAPPED BY THE USE OF DEBRIS BASINS, SILT FENCE, SILT TRAPS, OR SIMILAR MEASURES UNTIL THE DISTURBED AREA IS STABILIZED.
- ADEQUATE PROVISIONS SHALL BE PROVIDED TO MINIMIZE DAMAGE FROM SURFACE WATER TO THE CUT FACE OF SAVATIONS OR THE SLOPING SURFACES OF FILLS.
- 9) CUTS AND FILLS WILL NOT ENDANGER ADJOINING PROPERTY
- 10) FILLS WILL NOT ENCROACH UPON NATURAL WATER COURSES OR CONSTRUCTED CHANNELS IN A MANNER SO AS TO ADVERSELY AFFECT OTHER PROPERTY DWINERS
- 11) GRADING EQUIPMENT WILL CROSS FLOWING STREAMS BY THE MEANS OF BRIDGES OR CULVERTS, EXCEPT WHEN SUCH METHODS ARE NOT FEASIBLE. PROVIDED IN ANY CASE THAT SUCH CROSSINGS ARE KEPT TO A MINIMUM.
- PROVISIONS ARE PROVIDED FOR TREATMENT OR CONTROL OF ANY SOURCE OF SEDIMENTS AND ADEQUATE SEDIMENTATION TROL FACILITIES TO RETAIN SEDIMENTS ON SITE OR PRECLUDE SEDIMENTATION OF ADJACENT WATERS BEYOND THE LEVELS 100001; OR SPECIFIED IN THE GENERAL MYDES PERMIT NUMBER. 13) NO CONSTRUCTION ACTIVITIES SHALL BE CONDUCTED WITHIN A 25 FOOT BUFFER ALONG THE BANKS OF ALL STATE WATERS
- AS MEASURED HORIZONTALLY FROM THE POINT WHERE VEGETATION HAS BEEN WRESTED BY NORMAL STREAM FI ACTION, EXCEPT WHERE THE DIRECTOR OF EPD HAS DETERMINED TO ALLOW A VARIANCE THAT IS AT LEAST AS NATURAL RESOURCES AND THE ENVIRONMENT IN ACCORDANCE WITH THE PROVISIONS OF O.C. GA. 12-7-6. OR HEF TRUCTURE OR A ROADWAY STRUCTURE MUST BE CONSTRUCTED, PROVIDED THAT ADEQUATE EROSION CON RE INCORPORATED IN THE PROJECT PLANS AND SPECIFICATIONS AND ARE IMPLEMENTED.

14) NO CONSTRUCTION ACTIVITIES SHALL BE CONDUCTED WITHIN A 50 FOOT BUFFER, AS MEASURED HORIZONTALLY FROM THE POINT WHERE VEGETATION HAS BEEN WRESTED BY NORMAL STREAM FLOW OR WAVE ACTION, ALONG THE BANKS OF ANY STREAM WATERS CLASSIFIED AS TROLD STREAMS' EXCEPT WHEN APPROVAL IS GRANTED BY THE DIRECTOR OF EPE FOR ALTERNATE BUFFER REQUIREMENTS IN ACCORDANCE WITH THE PROVISIONS OF O. C. G.A. 12-76, OR WHERE A ROADWAY DRAINAGE STRUCTURE MUST BE CONSTRUCTED. PROVIDED, HOWEVER, THAT SMALL SPRINGS AND STREAMS CLASSIFIED AS TROUT STREAMS' WHICH DISCHARGE AN AVERAGE ANNUAL FLOW OF 25 GALLONS PER MINUTE OR LESS SHALL HAVE A 25 FOOT BUFFER OR THEY MAY BE PIPED. AT THE BIOSCRETION OF THE PERMITTER P. PURSUANT TO THE TERMS OF A RULE PROVIDING FOR A GENERAL VARIANCE PROMILGATED BY THE BOARD OF NATURAL RESOURCES INCLIDING NOTIFICATION OF SUCH TO EPO AND THE LOCAL ISSUING AUTHORITY OF THE LOCATION AND EXTENT OF THE PIPMS AND PRESCRIBED METHODIOLOF SOR MINIMIZING THE BUFFER REQUIREMENT FOR ANY ADJACENT TROUT STREAM FERMITTEES PROPERTY. AND THE PERMITTEE MUST COMPLY WITH HE BUFFER REQUIREMENT FOR ANY ADJACENT TROUT STREAM PERMITTEES PROPERTY.

FOR COMMON DRAINAGE LOCATIONS A TEMPORARY (OR PERMANENT) SEDIMENT RASIN PROVIDING AT LEAST 67 CHRIC YARDS 15) FOR COMMON DRAINAGE LOCATIONS A LEMPORARY (OR PERMANENT) SEDIMENT BASIN PROVIDING AT LEAST BY CUSTOR OF STORAGE PER ACRE DRAINED, OR EQUIVALENT CONTROL MEASURES, SHALL BE PROVIDED UNTIL FINAL STABLIZATION STEE. THE BY CUBIC YARDS OF STORAGE AREA PER ACRE DRAINED DOES NOT APPLY TO FLOWS FROM OFF-SITE AREAS AND FLOWS FROM ONSTER AREA STHAT ARE EITHER UNDISTURBED OR HAVE UNDERGOODE FINAL STABLIZATION WHERE SUCH F ARE DIVERTED AROUND BOTH THE DISTURBED AREA AND THE SEDIMENT BASIN, FOR DRAINAGE LOCATIONS WHERE A TEMPORARY SEDIMENT BASIN PROVIDING AT LEAST 67 CUBIC YARDS OF STORAGE PER ACRE DRAINED, OR EQUIVALENT CONTROLS IS NOT ATTAINABLE, SEDIMENT TRAPS, SLIT FENCES, OR EQUIVALENT SEDIMENT CONTROLS ARE REQUIRED FOR ALL SIDE SLOPE AND DOWN SLOPE BOUNDARIES OF THE CONSTRUCTION AREA. WHEN THE SEDIMENT FILLS TO A VOLUME AT MOST OF 22 CUBIC YARDS PER ACRE FOR EACH DRAINAGE AREA, THE SEDIMENT SHALL BE REMOVED TO RESTORE THE ORIGINAL DESIGN COLUME. THIS SEDIMENT MUST BE PROPERLY DISPOSED. SEDIMENT BASINS MAY NOT BE APPROPRIATE AT SOME CONSTRUCTION

- 6) NO SOLID MATERIALS, INCLUDING BUILDING MATERIALS, SHALL BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS A LITHORIZED BY A SECTION AND FERMIT
- 17) OFF SITE VEHICLE TRACKING OF DIRT, SOILS, AND SEDIMENTS AND THE GENERATION OF DUST SHALL BE MINIMIZED OR FUNDING TO THE MAXIMUM EXTENT PRACTICAL
- 18) ALL LOTS AND DEVELOPMENT AREAS SHALL MAINTAIN COMPLIANCE WITH APPLICABLE STATE AND/OR LOCAL WASTE DISPOSAL, SANITARY SEWER OR SEPTIC SYSTEM REGULATIONS.
- 9) A COPY OF THE APPROVED LAND DISTURBANCE PLAN AND PERMIT SHALL BE PRESENT ON THE SITE WHENEVER LA

20) THERE SHALL BE NO ON-SITE STORAGE OF PETROLEUM, MOBILE PETROLEUM TRUCKS SHALL BE USED TO FUE 20) THERE SHALL BE NO ON-SITE STORAGE OF PETROLEOM, MOBILE PETROLEOM NUCLOS SHALL BE USED TO FUEL. CONSTRUCTION COUPMENT ON SITE. NOTHING IN THIS PERMIT SHALL BE CONSTRUED TO PRECLUDE THE INSTITUTION OF ANY LEGAL ACTION OR RELIEVE THE PERMITTEE FROM ANY RESPONSIBILITIES, LIABILITIES, OR PENALTIES TO WHICH THE PERMITTEE OR MAY BE SUBJECT UNDER THE GEORGIA HAZARDOUS WASTE MANAGEMENT ACT, O.C.G.A. 12-8-60, ET SEQ. OR UNDER CHAPTER 14 OF TITLE 12 OF THE OFFICIAL CODE OF GEORGIA ANNOTATED, NOR IS THE OPERATOR RELIEVED FROM ANY RESPONSIBILITIES, LIABILITIES OR PENALTIES TO WHICH THE PERMITTEE IS OR MAY BE SUBJECT UNDER SECTION 311 OF THE CLEAN WATER ACT OR SECTION 106 OF COMPREHENSIVE ENVIRONMENTAL RESPONSE COMPENSATION AND LIABILITY ACT.

22) AMENDMENTS/REVISIONS TO THE ES&PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMP'S WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.

23) THE DESIGN PROFESSIONAL OR DESIGNEE IS TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL EMP'S WITHIN 7 DAYS AFTER INSTALLATION.

PERMITTEE REQUIREMENTS FOR INSPECTION:

1) EACH DAY WHEN ANY TYPE OF CONSTRUCTION ACTIVITY HAS TAKEN PLACE AT A PRIMARY PERMITTEE'S SITE, CERTIFIED PERSONNEL PROVIDED BY THE PRIMARY PERMITTEE SHALL INSPECT: (A) ALL AREAS AT THE PRIMARY PERMITTEES SITE WHERE PETROLEUM PRODUCTS ARE STORED, USED, OR HANDLED FOR SHILLS AND LEAST, FROM VEHICLES, AND EQUIPMENT, (B) ALL LOCATIONS AT THE PRIMARY PERMITTEE'S SITE WHERE VEHICLES ENTER OR EXIT THE SITE FOR EVIDENCE OF OFF-SITE SEDIMITACKING, AND (C) MEASURE RAINFALL CONCE EACH 24 HOUR PERIOD AT THE SITE. THESE INSPECTIONS MUST BE CONDUCTED UNTIL A NOTICE OF TERMINATION IS SUBMITTED.

UNTIL A NOTICE OF TERMINATION IS SUBMITTED.

2) CERTIFIED PERSONNEL, IPPOUNDED BY THE PRIMARY PERMITTEE) SHALL INSPECT THE FOLLOWING AT LEAST ONCE EVERY SEVEN (7) CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM THAT IS 0.5 INCHES RAINFALL OR GREATER (UNLESS UCH STORM ENDS AFTER 50.0 HOW ANAY FRIDAY OR ON ANY NON-WORKING STURDAY, ON-WORKING SUNDAY OR PAY NON-WORKING STURDAY, ON-WORKING SUNDAY OR PAY NON-WORKING STURDAY OR ANY NON-WORKING STURDAY OR ANY NOR STREAM HOULDAY IN WHICH CASE THE INSPECTION SHALL BE COMPLETED BY THE END OF THE NEXT BUSINESS DAY ANDOR WORKING DAY, WHICHEVER OCCURS FIRST; (A) DISTURBED AREAS OF THE PRIMARY PERMITTEE FOR STORAGE OF MATERIALS THAT HAVE NOT UNDERGONE FINAL STABILIZATION, (8) AREAS USED BY THE PRIMARY PERMITTEE FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION THAT HAVE NOT UNDERGONE FINAL STABILIZATION; AND (5) STRUCTURAL CONTROL MEASURES. EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN APPLICABLE TO THE PRIMARY PERMITTEE FOR STORAGE OF PRIMATERS IS STEED SHALL BE OSBERIVED TO BENINGE THAT THEY ARE OPERATING ORSPECTLY. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTINGS SIGNIFICANT IMPACTS TO RECEIVED WATER THAT HAVE UNDERGONE FINAL STABILIZATION. THE PERMITTEE MUST COMPLY WITH PART IV.D.4.4.(3). THESE INSPECTIONS MUST BE CONDUCTED UNTIL A NOTICE OF TERMINATION IS SUBMITTED.

3) CERTIFIED PERSONNEL (PROVIDED BY THE PRIMARY PERMITTEE) SHALL INSPECT AT LEAST ONCE PER MONTH DURING THE TERM OF THIS PERMIT (I.E., UNTIL A NOTICE OF TERMINATION IS RECEIVED BY EPD) THE AREAS OF THE SITE THAT HAVE UNDERGONE FINAL STABILIZATION. THESE AREAS SHALL BE INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM AND THE RECEIVING WATER(S), EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. WHERE DISCHARGE LOCATIONS OR POINTS E ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN EVENTING SIGNIFICANT IMPACTS TO RECEIVING WATER(S).

BASED ON THE RESULTS OF EACH INSPECTION, THE SITE DESCRIPTION AND THE POLLUTION PREVENTION AND CONTROL MEASURES IDENTIFIED IN THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN, THE PLAN SHALL BE REVISED AS APPROPRIATE NOT LATER THAN SEVEN (7) CALENDAR DAYS FOLLOWING EACH INSPECTION, IMPLEMENTATION OF SUCH CHANGES SHALL BE MADE AS SOON AS PRACTICAL BUT IN NO CASE LATER THAN SEVEN (7) CALENDAR DAYS FOLLOWING EACH INSPECTION

5) A REPORT OF EACH INSPECTION THAT INCLUDES THE NAME(S) OF PERSONNEL MAKING EACH INSPECTION, THE DATE(S) OF EACH INSPECTION, MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THE ERGISION, SEDIMENTATION AND POLLUTION CONTROL, PLAN, AND ACTIONS TAKEN IN ACCORDANCE WITH PART IV, DA 4,4(s) OF THE PERMIT SHALL BE MADE AND RETAINED AT THE SITE OR BE READILY AVAILABLE AT A DESIGNATED ALTERNATE LOCATION UNTIL THE ENTIRE SITE OR THAT PORTION OF A CONSTRUCTION PROJECT THAT HAS BEEN PHASED HAS UNDERGONE FINAL STRAILIZATION AND A MOTICE OF TERMINATION IS SUBMITTED TO EPD. SUCH REPORTS SHALL IDENTIFY ANY INCIDENTS OF NON-COMPILANCE. HE REPORT SHALL CONTRAIL OF THE ACTION OF THE STRAIL SENDED HAS UNDERGONE OF THE ACTION OF THE STRAIL SENDED HAS UNDERGONE OF THE STRAIL SENDED HAS UNDERGONE OF THE STRAIL SENDED HAS UNDERGONE. OF THIS PERMIT. THE REPORT SHALL CONTRAIL DESIGNED IN ACCORDANCE WITH THE REPORT SHOULD OF THIS PERMIT.

SAMPLING FREQUENCY:

- THE PRIMARY PERMITTEE MUST SAMPLE IN ACCORDANCE WITH THE PLAN AT LEAST ONCE FOR EACH RAINFALL EVENT SCRIBED BELOW. FOR A QUALIFYING EVENT, SAMPLES MUST BE TAKEN WITHIN FORTY-FIVE (45) MINUTES OF:
- A) THE ACCUMULATION OF THE MINIMUM AMOUNT OF RAINFALL FOR THE QUALIFYING EVENT, IF THE STORMWATER DISCHARGE TO A MONITORED RECEIVING WATER OR FROM A MONITORED OUTFALL HAS BEGUN AT OR PRIOR TO THE ACCUMULATION,
- THE BEGINNING OF ANY STORM WATER DISCHARGE TO A MONITORED RECEIVING WATER OR FROM A MONITORED OUTFALL IF THE DISCHARGE BEGINS AFTER THE ACCUMULATION OF THE MINIMUM AMOUNT OF RAINFALL FOR THE QUALIFYING EVEN
- 2) HOWEVER, WHERE MANUAL AND AUTOMATIC SAMPLING ARE IMPOSSIBLE (AS DEFINED IN THIS PERMIT), OR ARE BEYOND THE PERMITTEES CONTROL. THE PERMITTEE SHALL TAKE SAMPLES AS SOON AS POSSIBLE, BUT IN NO CASE MORE THAN TWELVE (12) HOURS AFFER THE BEGINNING OF THE STORM WATER DISCHARGE.
- 3) SAMPLING BY THE PERMITTEE SHALL OCCUR FOR THE FOLLOWING EVENTS:
- A) FOR EACH AREA OF THE SITE THAT DISCHARGES TO A RECEIVING STREAM, THE FIRST RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH AND ALLOWS FOR MONITORING DURING NORMAL BUSINESS HOURS* (MONDAY THRU FRIDAY, 8:00 AI 5:00 PM AND SATURDAY 8:00 AM TO 5:00 PM, EXCLUDING ALL NON-WORKING FEDERAL HOLIDAYS, WHEN CONSTRU ACTIVITY IS BEING CONDUCTED BY THE PRIMARY PERMITTEE) THAT OCCURS AFTER ALL CLEARING AND GRUBBIN
- OPERATIONS HAVE BEEN COMPLETED IN THE DRAINAGE AREA OF THE LOCATION SELECTED AS THE SAMPLING LOCATION IN ADDITION TO (1,) ABOVE, FOR EACH AREA OF THE SHITE THAT DISCHARGES TO A RECEIVING STREAM, THE FIRST RAN EVENT THAT REACHES OR EXCEEDS 0.5 INCH AND ALLOWS FOR MONITORING DURING NORMAL BUSINESS HOURS' THAT
- EVENT THAT REACHES OR EXCEEDS 6.5 INCH AND ALLOWS FOR MONTORING DURING NORMAL BUSINESS HOURS' THAT COUNTS THAT THE PLATE THE FIRST SAMPLING EVENT OR AFTER ALL MASS GRADING OPERATIONS HAVE BEEN OWNETED IN THE DRAINAGE AREA OF THE LOCATION SELECTED AS THE SAMPLING LOCATION, WHICHEVER COMES RIFST OF THE TIME OF SAMPLING PERFORMED PURSUANT TO (1) AND (2) ABOVE, IF BMPS ARE FOUND TO BE PROPERTY DESIGNED INSTALLED AND MAINTAINED, NO FURTHER ACTION IS REQUIRED. IF BMPS IN ANY AREA OF THE SITE THAT DISTANCED FOR THE PLATE OF THE STEED AND MAINTAINED, CORRECTIVE ACTION SHALLED BEFINED. HAND IMPLEMENTED WITHIN TWO (P.S.M.) I DESIGNED, INSTRUCED AND MININFARINED, CONTRICTIVE ACTIONS SHALL BE DESIGNED.

 THAT AREA OF THE SITE FOR EACH SUBSEQUENT RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH DIVING NORMAL

 BUSINESS HOURS 'UNTIL THE SELECTED TURBUITY STAMPOR IS ATTAINED. OR UNTIL POST-STORM EVENT INSPECTIONS. TERMINE THAT BMPS ARE PROPERLY DESIGNED INSTALLED AND MAINTAINED: AND
- DETERMINE THAT BMPS ARE PROPERLY DESIGNED, INSTALLED AND MAINTAINED, AND
 EXISTING CONSTRUCTION ACTIVITIES, I.E., THOSE THAT ARE OCCURRING ON OR BEFORE THE EFFECTIVE DATE OF THIS
 PERMIT, THAT HAVE MET THE SAMPLING REQUIRED BY (1), ABOVE SHALL SAMPLE IN ACCORDANCE WITH (2), THOSE EXIST
 CONSTRUCTION ACTIVITIES THAT HAVE MET THE SAMPLING REQUIRED BY (2), ABOVE SHALL NOT BE REQUIRED TO CONDITIONAL SAMPLING OTHER THAN AS REQUIRED BY (3), ABOVE.

NOTE THAT THE PERMITTEE MAY CHOOSE TO MEET THE REQUIREMENTS OF (A.) AND (B.) ABOVE BY COLLECTING TURBIDITY SAMPLES FROM ANY RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH AND ALLOWS FOR MONITORING AT ANY TIME OF THE DAY OR WEEK.

SAMPLING REQUIREMENTS:

THIS PERMIT REQUIRES THE MONITORING OF NEPHELOMETRIC TURBIDITY IN RECEIVING WATER(S) OR OUTFALLS IN ACCORDANCE WITH THIS PERMIT. THIS IS NOT APPLICABLE TO SECONDARY PERMITTEES. THE FOLLOWING PROCEDURES CONSTITUTE EPD'S GUIDELINES FOR SAMPLING TURBIDITY.

SAMPLE TYPE ALL SAMPLING SHALL BE COLLECTED BY "GRAB SAMPLES" AND THE ANALYSIS OF THESE SAMPLES MUST BE CONDUCTED IN ACCORDANCE WITH METHODOLOGY AND TEST PROCEDURES ESTABLISHED BY 40 CFR PART 136 (UNLESS OT TROCEDURES HAVE BEEN APPROVED; THE GUIDANCE DOCUMENT STITLED YNDES STORMWATER SAMPLING GUIDANCE DOCUMENT, EPA 833-94-2011 AND GUIDANCE DOCUMENTS THAT MY BE PREPARED BY THE EPA.

- AMPLE CONTAINERS SHOULD BE LABELED PRIOR TO COLLECTING THE SAMPLES.
- SAMPLES SHOULD BE WELL MIXED BEFORE TRANSFERRING TO A SECONDARY CONTAINER. STATE OF GEORGIA PAGE 23 OF 33 DEPARTMENT OF NATURAL RESOURCES FERMIT NO. GARTOODOT ENVIRONMENTAL PROTECTION DIVISION. LARGE MOUTH, WELL CLEANDE AND RINSED GLASS OR PLASTIC, JARS SHOULD BE USED FOR COLLECTING SAMPLES. THE JARS SHOULD BE CLEANED THOROUGHLY TO AVOID CONTAININATION.
- JARS SHOULD BE CLEAVED THOROUGHLY TO AVOID CONTAMINATION.

 MANUAL, AUTOMATIC OR RISING STAGE SAMPLING MAY BE UTILIZED. SAMPLES REQUIRED BY THIS PERMIT SHOULD BE
 ANALYZED IMMEDIATELY, BUT IN NO CASE LATER THAN 48 HOURS AFTER COLLECTION, HOWEVER, SAMPLES FROM
 AUTOMATIC SAMPLES MUST SE COLLECTED NO LATER THAN THE NEXT BUSINESS DAY AFTER THER ACCUMULATION,
 UNLESS FLOW THROUGH AUTOMATED ANALYSIS IS UTILIZED. DILLUTION OF SAMPLES IS NOT REQUIRED. SAMPLES MAY SE
 ANALYZED DIRECTLY WITH A PROPERTY CALIBRATED TURBEIDMETER, SAMPLES ARE NOT REQUIRED TO BE COOLCE.
- SAMPLING AND ANALYSIS OF THE RECEIVING WATER(S) OR OUTFALLS BEYOND THE MINIMUM FREQUENCY STATED IN THIS PERMIT MUST BE REPORTED TO EPD AS SPECIFIED IN PART IV.E.
- A COMBINATION OF RECEIVING WATER(S) AND OUTFALL(S). SAMPLES TAKEN FOR THE PURPOSE OF COMPLIANCE WITH THIS PERMIT SHALL BE REPRESENTATIVE OF THE MONITORED ACTIVITY AND REPRESENTATIVE OF THE WATER QUALITY OF THE RECEIVING WATER(S) ANDIOR THE STORM WATER OUTFALLS USING THE FOLLOWING MINIMUM GUIDELINES:
- THE UPSTREAM AND LE FOR EACH RECEIVING MATERIAL SUBMATER FACE TAKEN IMMEDIATELY UPSTREAM OF THE CONFLUENCE OF THE FIRST STORM WATER DISCHARGE FROM THE PERMITTED ACTIVITY (I.E., THE DISCHARGE FARTHEST UPSTREAM AT THE SITE) BUT DOWNISTREAM OF ANY OTHER STORM WATER DISCHARGE FARTHEST UPSTREAM AT THE SITE) BUT DOWNISTREAM OF ANY OTHER STORM WATER DISCHARGES NOT ASSOCIATED WITH THE PERMITTED THE SHEED BY JUDINEST REAM UP ANY OTHER STUMBLY MALEN DISCHARGES NOT ASSOCIATED WITH THE PERMITTED ACTIVITY. WHERE APPROPARTIE, SEVERAL UPSTREAM SAMPLES FROM ACROSS THE RECEIVING WATER(S) MAY NEED TO BE TAKEN AND THE ARITHMETIC AVERAGE OF THE TURBIDITY OF THESE SAMPLES USED FOR THE UPSTREAM TURBIDITY ALLE.
- VALUE.

 THE DOWNSTREAM SAMPLE FOR EACH RECEIVING WATER(S) MUST BE TAKEN DOWNSTREAM OF THE CONFLUENCE OF THE LAST STORM WATER DISCHARGE FROM THE PERMITTED ACTIVITY (LE. THE DISCHARGE FARTHEST DOWNSTREAM AT THE SITE) BUT UPSTREAM OF ANY OTHER STORMWISTED BISCHARGE FOR OTA ASSOCIATED WITH THE PERMITTED ACTIVITY. WHERE APPROPRIATE, SEVERAL DOWNSTREAM SAMPLES FROM ACROSS THE RECEIVING WATER(S) MAY NEED TO BE TAKEN AND THE ARTIMENT CA VERGAGE OF THESE SAMPLES USED FOR THE DOWNSTREAM TURBITITY VALUE.

RETENTION OF RECORDS:

- THE PRIMARY PERMITTEE SHALL RETAIN THE FOLLOWING RECORDS AT THE CONSTRUCTION SITE OR THE RECORDS SHALL B
 READLY AVAILABLE AT A DESIGNATED ALTERNATE LOCATION FROM COMMENCEMENT OF CONSTRUCTION UNTIL SUCH TIME AS A
 NOT IS SUBMITTED IN ACCORDANCE WITH PARTY.
- A) A COPY OF ALL NOTICES OF INTENT SUBMITTED TO EPD:
- A COPY OF THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN REQUIRED BY THIS PERMIT THE DESIGN PROFESSIONAL'S REPORT OF THE RESULTS OF THE INSPECTION CONDUCTED IN ACCORDANCE WITH PART IV.A.S. OF THIS PERMIT;

- A COPY OF ALL INSPECTION REPORTS GENERATED IN ACCORDANCE WITH PART IV.D.4.A. OF THIS PERMIT; A COPY OF ALL VIOLATION SUMMARIES AND VIOLATION SUMMARY REPORTS GENERATED IN ACCORDANCE WITH PART III.D.2. OF THIS DEPART. AND DAILY RAINFALL INFORMATION COLLECTED IN ACCORDANCE WITH PART IV.D.4.A.(1)(C) OF THIS PERMIT
- COPIES OF ALL NOIS NOT'S REPORTS PLANS MONITORING REPORTS MONITORING INFORMATION INCLUDING ALL 2) COPIES OF ALL NOTS, NOTS, REPORTS, PLANS, MONITORING REPORTS, MONITORING INFORMATION, INCLUDING ALL CALBRATION AND MAINTENANCE RECORDS AND ALL ORIGINALS TIPIN CHART RECORDINGS FOR CONTINUOUS MONITORING INSTRUMENTATION, EROSION, SEDIMENTATION AND POLLUTION CONTROL PLANS, RECORDS OF ALL DATA USED TO COMPLETE THE NOTICE OF INTENT TO BE COVERED BY THIS PERMIT AND ALL OTHER RECORDS REQUIRED BY THIS PERMIT SHAPE THE NOTICE OF A TENTON THE OFFICE OF THE PERMIT AND ALL OF PERMIT OF A THE PERMIT THE PERMIT THE AUTHOR OF THE PERMIT THE THE YEARS FROM THE DATE HAT THE NOTI IS SUBMITTED IN ACCORDANCE WITH PART VIO FINE PERMIT. THESE RECORDS MUST BE MAINTAINED AT THE PERMITT THE THE AUTHOR OF THE PERMIT THE OWN WRITTEN AS CLASED AT THE PERMIT THE SITE. THE PERMIT THE OWN WRITTEN THE PERMIT THE OWN WRITTEN THE PERMIT THE OWN WRITTEN THE PERMIT THE OWN THE THE PERMIT THE OWN THE THE PERMIT THE OWN THE THE OWN THE OWN WRITTEN THE PERMIT THE OWN THE THE OWN THE OWN WRITTEN THE OWN THE OWN

1) THE APPLICABLE PERMITTEES ARE REQUIRED TO SUBMIT A SUMMARY OF THE MONITORING RESULTS TO THE EPD AT THE ADDRESS SHOWN IN PART II.C. BY THE FIFTEENTH DAY OF THE MONTH FOLLOWING THE REPORTING PERIOD. REPORTING PERIOD ARE MONTHS DURING WHICH SHE MANNIES ARE TAKEN IN ACCORDANCE WITH THIS PERMIT. SAMPLING RESULTS SHAND RESULTS THAT CLEARLY LEGIBLE FORMAT. UPON WRITTEN NOTIFICATION, EPD MAY REQUIRE THE APPLICABLE PERMITTEE TO SUBMIT THE SAMPLING RESULTS ON A MORE FREQUENT BASS. SAMPLING REDAY OF ANY STORM WATER DISCHARGES OR THE RECEIVING WATER(S) BEYOND THE MINIMUM PREQUENCY STATED IN THIS PERMIT MUST BE REPORTED IN A SIMILAR MANNER TO THE EPD. THE SAMPLING REPORTS MUST BE SUBMITTED TO EPD UNTIL SUCH TIME AS A NOT IS SUBMITTED IN ACCORDANCE WITH PART V. G. SAMPLING REPORTS MUST BE SUBMITTED TO EPD UNTIL SUCH TIME AS A NOT IS SUBMITTED IN ACCORDANCE WITH PART V. G. SAMPLING REPORTS MUST BE SUBMITTED.

2) ALL WRITTEN CORRESPONDENCE REQUIRED BY THIS PERMIT SHALL BE SUBMITTED BY RETURN RECEIPT CERTIFIED MAIL (OR SIMILAR SERVICE) TO THE APPROPRIATE DISTRICT OFFICE OF THE EPD ACCORDING TO THE SCHEDULE IN APPENDIX A OF THIS EVERMIT. THE PERMITTEE SHALL RETAIN A COPY OF THE PROOF OF SUBMITTAL AT THE CONSTRUCTION SITE OR THE PROOF OF SUBMITTAL SHALL BE READILY AVAILABLE AT A DESIGNATED LOCATION FROM COMMENCEMENT OF CONSTRUCTION UNTIL SUCH TIME AS AN OT IS SUBMITTED IN ACCORDANCE WITH PART VI.

- 3) ALL MONITORING RESULTS SHALL INCLUDE THE FOLLOWING INFORMATION:
- A) THE DATE, EXACT PLACE, AND TIME OF SAMPLING OR MEASUREMENTS:
- THE NAME(S) OF THE INDIVIDUAL(S) WHO PERFORMED THE SAMPLING AND MEASUREMENTS:
- THE DATE(S) ANALYSES WERE PERFORMED: THE TIME(S) ANALYSES WERE INITIATED:
- THE NAME(S) OF THE INDIVIDUAL(S) WHO PERFORMED THE ANALYSES:
- REFERENCES AND WRITTEN PROCEDURES, WHEN AVAILABLE, FOR THE ANALYTICAL TECHNIQUES OR METHODS, USED: AND The respectives and which have recovered the second of the respective second of the resolution of the

WASTE DISPOSAL:

WASTE MATERIALS: ALL SANITARY WASTE UNITS WILL BE LOCATED IN ONE AREA WHERE THE LIKELIHOOD OF THE UNIT VADLE MILETAND. ALL AGMILATY WAS IE UNILS WILL BE LUCALIEU IN USE AREA WHITEEN ITELE MEDICAL PROPERTIES. BEING MILETAN WATER DISCHARGE IS NEGLIGIBLE, ADDITIONAL CONTAINMENT BMFS IMESTE IMPLEMENTED, SUCH AS EL BAGS OR SPECIALLY DESIGNED PLASTIC SKID CONTAINERS AROUND THE SASE TO PREVENT WASTES FROM CONTRIBUTING OWN WATER DISCHARGES. THE LOCATION OF SANTARY WASTE UNITS MUCH BESTE IDENTIFIED ON THE ESSAP OF AN BY THE

HAZARDOUS WASTE: ALL HAZARDOUS WASTE MATERIALS WILL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL 2) HAZAROOUS WASTE: ALL HAZAROOUS WASTE MATERIALS WILL BE DISPOSED OF IN THE MANNER SPECIFIED BY LUCAL. STATE ANDOR FEDERAL REGULATION AND BY THE MANNER AFCHERED BY LUCAL STATE ANDOR FEDERAL REGULATION AND BY THE MANNER AFCHERED BY LUCAL STATE AND STATE WASTE AND STATE AND STATE WASTE AND STATE AND STATE

3) THE CONTRACTOR WILL IMPLEMENT THE SPILL PREVENTION CONTROL AND COUNTERMEASURES (SPCC) PLAN FOUND WITTHE ESPOP AND WILL TRAIN ALL PERSONNEL IN THE PROPER CLEANLY AND HANDLING OF SPILLED MATERIALS, ON SPILLED HAZARDOUS WASTES WILL BE ALLOWED TO COME IN CONTRACT WITH STORMWATER DISCHASSES. SIGH CONTRACT OCCURS, THE STORMWATER DISCHASGE WILL BE CONTRINED ON SITE UNTIL APPROPRIATE MEASURE IN COMPLIANCE WITH STATE AND FEDERAL REGULATIONS ARE TAKEN TO DISPOSE OF SUCH CONTRAINANCED STORMWATER. IT SHE THE RESPONSIBILITY OF THE JOB SITE SUPERINTENDENT TO PROPERTY TRAIN ALL PERSONNEL IN THE USE OF THE SPOC PLAN.

A MINIMUM OF ONE PORTABLE SANITARY UNIT WILL BE PROVIDED FOR EVERY TEN (10) WORKERS ON SITE. ALL SANITARY WASTI L BE COLLECTED FROM THE PORTABLE UNITS A MINIMUM OF ONE TIME PER WEEK BY A LICENSED PORTABLE FACILITY PROVIDER OMPLETE COMPLIANCE WITH LOCAL AND STATE REGULATIONS.

5) SANITARY SEWER WILL BE PROVIDED BY MUNICIPAL AUTHORITY/SEPTIC SYSTEM AT THE COMPLETION OF THIS PROJECT

SPILL PREVENTION AND CONTROL NOTES:

TENANCE OF SUCH EQUIPMENT. EQUIPMENT MAINTENANCE AREAS WILL BE LOCATED AWAY FROM STATE WATERS, NATUR. IS AND STORM WATER DRAINAGE INLETS. IN ADDITION, TEMPORARY PUELIND TANDS SHALL HAVE A SCENDAP FORDER IT OP REVENTINMINIZE SITE CONTAMINATION. DISCHARGE OF OILS. FUELS AND LUBRICANTS IS PROHIBITED. PROPER DISP LINER TO PREVENT/MINIMIZE STITE CONTAMINATION. DISCHARGE OF OILS, FUELS AND EUBRICAINTS IS PROFIBITED. PROFER DISPOS METHODS WILL INCLUDE COLLECTION IN A SUITABLE CONTAINER AND DISPOSAL AS REQUIRED BY LOCAL AND STATE REGULATIONS

- 2) FERTILIZERSHERBICIDES-THESE PRODUCTS WILL BE APPLIED AT RATES THAT DO NOT EXCEED THE MANUFACTURER'S SPECIFICATIONS OR ABOVET THE GUIDELINES SET FORTH IN THE CROP ESTABLISHMENT OR IN THE GSWCC MANUAL FOR EROSION NAD SEDIMENT CONTROL IN GEORGIA, ANY STORAGE OF THESE MATERIALS WILL BE UNDER ROOF IN SEALED CONTAINED.
- 4) AN EFFORT WILL BE MADE TO STORE ONLY ENOUGH PRODUCT REQUIRED TO DO THE JOB
- 5) ALL MATERIALS STORED ONSITE WILL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS.
- PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL MANUFACTURER'S LABEL
- 7) SUBSTANCES WILL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER 8) WHENEVER POSSIBLE. ALL OF A PRODUCT WILL BE USED UP BEFORE DISPOSING OF THE CONTAINER
- 9) MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL WILL BE FOLLOWED
- 10) THE SITE SUPERINTENDENT WILL INSPECT DAILY TO ENSURE PROPER USE AND DISPOSAL OF MATERIALS ONSITI
- PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS UNLESS THEY ARE NOT RE-SEALABLE. ORIGINAL LABELS AND MATERIAL SAFETY DATA WILL BE RETAINED.
- C) IF SURPLUS PRODUCT MUST BE DISPOSED OF, MANUFACTURER'S OR LOCAL AND STATE RECOMMENDED METHODS FOR PROPER DISPOSAL WILL BE FOLLOWED.

12) MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES.

13) MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREAS TYPICAL MATERIALS AND EQUIPMENT INCLUDES, BUT IT NOT LIMITED TO, BROOMS, DUSTPANS, MOPS, RAGS, GLOVES, GOGGLES, CAT LITTER, SAND, SAWIDUST AND PROPERTY, LABELED PLASTIC, AND INSTELL WASTE CONTAINERS. 14) SPILL PREVENTION PRACTICES AND PROCEDURES WILL BE REVIEWED AFTER A SPILL AND ADJUSTED AS NECESSARY TO PREVENT FITTIBE SPILLS.

5) ALL SPILLS WILL BE CLEANED UP IMMEDIATELY UPON DISCOVERY. ALL SPILLS WILL BE REPORTED AS REQUIRED BY LOCAL, STATE 16) THE SPILL AREA WILL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A HAZARDOUS SUBSTANCE.

17) SPILLS OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF THE SIZE.

18) THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM RE-OCCURRINA AND HOW TO CLEAN UP THE SPILL, IF THERE IS ANOTHER ONE. A DESCRIPTION OF THE SPILL, WHAT CAUSED IT, AND THE CLEANUP MEASURES WILL ALSO BE INCLUDED.

21) BUILDING MATERIALS-NO BUILDING OR CONSTRUCTION MATERIALS WILL BE BURIED OR DISPOSED OF ONSITE. ALL SUCH MATERIAL WILL BE DISPOSED OF IN PROPER WASTE DISPOSAL PROCEDURES. 22) FOR SPILLS THAT IMPACT SURFACE WATER (LEAVE A SHEEN ON SURFACE WATER), THE NATIONAL RESPONSE CENTER (NRC)

23) FOR SPILLS OF AN UNKNOWN AMOUNT. THE NATIONAL RESPONSE CENTER (NRC) WILL BE CONTACTED WITHIN 24 HRS..

24) FOR SPILLS GREATER THAN 25 GALLONS AND NO SURFACE WATER IMPACTS OCCUR, THE GEORGIA EPD WILL BE CONTACTED WITHIN 24 HOURS.

25) SPILLS LESS THAN 25 GALLONS AND NO SURFACE WATER IMPACTS OCCUR, THE SPILL WILL BE CLEANED UP AND LOCAL AGENCIES WILL BE CONTACTED AS REQUIRED. 26) THE CONTRACTOR SHALL NOTIFY THE LICENSED PROFESSIONAL WHO PREPARED THIS PLAN IF MORE THAN 1320 G PETROLEUM IS STORED ONSITE (THIS INCLUDES CAPACITIES OF EQUIPMENT) OR IF ANY ONE PIECE OF EQUIPMENT HAS GREATER THAN 860 GALLONS. THE CONTRACTOR WILL NEED A SPILL PREVENTION CONTAINMENT AND COUNTERMEASI PREPARED BY THAT LICENSED PROFESSIONAL.

SITE DETAILS:

- NATURE OF THE CONSTRUCTION ACTIVITY = DEMOLITION AND DOG PARK DEVELOPMENT
- 2) CONSTRUCTION SCHEDULE = SEE G-
- 3) TOTAL AREA OF THE SITE = 1.618 ACRES 4) TOTAL DISTURBED AREA OF THE SITE = 1.618 ACRES
- 5) PRE-DEVELOPMENT CURVE NUMBER = 63.5
- 7) EXISTING TOPOGRAPHIC MAP = SEE SHEET SERIES V-1
- 8) PLAN INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER MAJOR GRADING ACTIVITIES = SEE SHEET C-2 9) PLAN INDICATING AREAS OF SOIL DISTURBANCE = SEE SHEET SERIES C-2
- 10) SEE SHEET SERIES C-4 FOR ALL STRUCTURAL AND NONSTRUCTURAL BMP'S. 11) IDENTIFICATION OF RECEIVING WATER(S) = TRIBUTARY OF NANCY CREEK
- 12) APPENDIX B RATIONALE
- A) TYPE OF STREAM = WARM WATER
 B) SURFACE DRAINAGE AREA = 0-4.9
 C) NTU ALLOWED VALUE = 75
- 13) BUFFERED STATE WATERS PRESENT ON SITE = NO KNOWN STATE WATERS WITHIN 200 FT OF SITE
- 14) WETLAND ACREAGE AT THE SITE = 0 ACRES OF KNOWN WETLANDS 15) NO PORTION OF THE SUBJECT PROPERTY LIES WITHIN A 100 YEAR FLOOD HAZARD AREA PER FIRM MAP NUMBER 13089C0016.
- 17) DESCRIPTION OF APPROPRIATE CONTROLS AND MEASURES THAT WILL BE IMPLEMENTED AT THE CONSTRUCTION SITE = SEE SHEET SERIES C-4

Foresite Group, Inc 5185 Peachtree Pkwy Norcross, GA 30092

f | 770,368,1944 w | www.fg-inc.ne

DEVEL OPER

PARK

DOG

RUN

ROOK

DEVELOPMENT RD. GEO RICT 4770 N. F ', DEKALI L.L. 354, **DESIGN**

DATE

1" = ---

PROJECT MANAGER .IV/W DRAWING BY: JURISDICTION: DUNWOODY, GA

EROSION CONTROL NOTES

SHEET NUMBER

COMMENTS:

SCALE:

TITI F:


REVISIONS

NOT RELEASED FOR CONSTRUCTION

JOB/FILE NUMBER

487.001

SEE SHEET SERIES C-4 FOR EROSION AND SEDIMENTATION CONTROL PLANS



NGINEER:


Foresite Group, Inc. 5185 Peachtree Pkwy. Suite 240 Norcross, GA 30092

o | 770.368.1399 f | 770.368.1944 w | www.fg-inc.net

DEVELOPER:

CONTACT:

BROOK RUN DOG PARK DESIGN DEVELOPMENT



DATE REVISIONS

PROJECT MANAGER:	JVW
DRAWING BY:	NJF
JURISDICTION:	DUNWOODY, GA
DATE:	9 AUGUST 2013
SCALE:	AS SHOWN
TITLE:	


PAVING DETAILS

SHEET NUMBER:

C-5

COMMENTS: NOT RELEASED FOR CONSTRUCTION

JOB/FILE NUMBER:



FORESITE group

Foresite Group, Inc. 5185 Peachtree Pkwy. Suite 240 Norcross, GA 30092

o | 770.368.1399 f | 770.368.1944 w | www.fg-inc.net


DEVELOPER:

CONTACT:

BROOK RUN DOG PARK DESIGN DEVELOPMENT

4770 N. PEACHTREE RD. VOODY, DEKALB COUNTY, GEORGIA L.L. 354, 18TH DISTRICT

ROJECT:



REVISIONS DATE

PROJECT MANAGER:	JVW
DRAWING BY:	NJF
JURISDICTION:	DUNWOODY, GA
DATE:	9 AUGUST 2013
SCALE:	AS SHOWN
TITLE:	

CONSTRUCTION DETAILS

SHEET NUMBER:


C-6

COMMENTS:

JOB/FILE NUMBER:

NOT RELEASED FOR CONSTRUCTION

4



1. PIPE BEDDING: SELECT COMMON FILL COMPACTED TO 95% OF THE MAXIMUM DENSITY AS PER AASHTO T-180.

2. TRENCH BACKFILL: COMMON FILL COMPACTED TO 95% OF THE MAXIMUM DENSITY AS PER AASHTO T-180. 3. (*): 15" MAX. (12" MIN.) FOR PIPE DIAMETER LESS THAN 24", AND 24" MAX (12" MIN.)FOR PIPE DIAMETER 24" AND LARGER.


4. WATER SHALL NOT BE PERMITTED IN THE TRENCH DURING CONSTRUCTION.


5. ALL PIPE TO BE INSTALLED WITH BELL FACING UPSTREAM TO THE DIRECTION OF THE FLOW.

6. REFER TO THE SECTION OF THE ALDOT STANDARDS FOR SHEETING AND BRACING IN EXCAVATIONS.

7. DEPTH FOR REMOVAL OF UNSUITABLE MATERIAL SHALL GOVERN DEPTH OF BEDDING ROCK BELOW THE PIPE. A CERTIFIED GEOTECHNICAL ENGINEER SHALL DETERMINE IN THE FIELD REQUIRED REMOVAL OF UNSUITABLE WATERIAL TO REACH SUITABLE FOUNDATION.


CLASS B BEDDING AND TRENCHING DETAIL C-7 NOT TO SCALE





SANITARY MANHOLE

NOT TO SCALE



NOTES:

1. ALL PIPE SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321, "STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY FLOW APPLICATIONS", LATEST ADDITION

3. FOUNDATION: WHERE THE TRENCH BOTTOM IS UNSTABLE, THE CONTRACTOR SHALL EXCAVATE TO A DEPTH REQUIRED BY THE ENGINEER AND REPLACE WITH SUITABLE MATERIAL AS SPECIFIED BY THE ENGINEER. AS AN ALTERNATIVE AND AT THE DISCRETION OF THE DESIGN ENGINEER, THE TRENCH BOTTOM MAY BE STABILIZED USING A GEOTEXTILE MATERIAL

4. <u>BEDDING:</u> SUITABLE MATERIAL SHALL BE CLASS I, II OR III. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. UNLESS OTHERWISE NOTED BY THE ENGINEER, MINIMUM BEDDING THICKNESS SHALL BE 4* (100mm) FOR 4*-24* (100mm-00mm), §* (150mm) FOR 30*-60* (750mm-900mm).

5. INITIAL BACKFILL: SUITABLE MATERIAL SHALL BE CLASS I, II OR III IN THE PIPE ZONE EXTENDING NOT LESS THAN 6° ABOVE CROWN OF PIPE. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. MATERIAL SHALL BE INSTALLED AS REQUIRED IN ASTM D2321, LATEST EDITION.

6. MINIMUM COVER: MINIMUM COVER, H, IN NON-TRAFFIC APPLICATIONS (GRASS OR LANDSCAPE AREAS) IS 12° FROM THE TOP OF PIPE TO GROUND SURFACE. ADDITIONAL COVER MAY BE REQUIRED TO PREVENT FLOATION. FOR TRAFFIC APPLICATIONS, MINIMUM COVER, H, IS 12° UP TO 48° DIAMETER PIPE AND 24° OF COVER FOR 54°-60° DIAMETER PIPE, MEASURED FROM TOP OF PIPE TO BOTTOM OF FLEXIBLE PAVEMENT OR TO TOP OF RIGID PAVEMENT.

HDPE BEDDING DETAIL

RECOMMENDED MINIMUM TRENCH WIDTHS

PIPE DIAM.	MIN. TRENCH WIDTH
4"	21"
6"	23"
8"	26"
10"	28"
12"	30"
15"	34"
18"	39"
24"	48"
30"	56"
36"	64"
42"	72"
48"	80"
54"	88"
60"	96"


5185 Peachtree Pkwy. Norcross, GA 30092

f | 770.368.1944 w | www.fg-inc.net

DEVELOPER:

BROOK RUN DOG PARK DESIGN DEVELOPMENT

4770 N. PEACHTREE R Y, DEKALB COUNTY, GF L.L. 354, 18TH DISTRIC



DATE REVISIONS

PROJECT MANAGER: JVW DRAWING BY: NJP JURISDICTION: DUNWOODY, GA 9 AUGUST 2013 SCALE: AS SHOWN TITLE:

UTILITIES DETAILS

SHEET NUMBER:

COMMENTS:


ც-7

NOT RELEASED FOR CONSTRUCTION

JOB/FILE NUMBER:


487.001

NOT TO SCALE




1. FENCE SHALL BE WIRE REINFORCED.

SILT FENCE DETAIL - TYPE C




Fr STONE FILTER RING



NOTE: THE CONSTRUCTION EXIT PAD SHALL BE AT LEAST 50 FEET IN LENGTH, SHALL OCCUPY THE FULL WIDTH OF VEHICLE EGRESS, AND SHALL BE COMPLETELY UNDERLAIN BY SUITABLE GEOTEXTILE.

TEMPORARY CONSTRUCTION EXIT (co NOT TO SCALE



NOTES:


1. L IS THE LENGTH OF THE RIPRAP APRON.

2. THICKNESS SHALL BE 1.5 TIMES THE MAXIMUM STONE DIAMETER BUT NOT LESS THAN 6".

3. IN A WELL-DEFINED CHANNEL EXTEND THE APRON UP THE CHANNEL BANKS TO AN ELEVATION OF 6" ABOVE THE TOP OF PIPE OR TO THE TOP OF FIPE OR TO THE TOP OF THE BANK, WHICHEVER IS LESS.


4. A FILTER BLANKET OR FILTER FABRIC SHELL BE INSTALLED BETWEEN THE RIPRAP AND SOIL FOUNDATION. 5. GRADED RIPRAP STONE (MIN. 50 LB. STONE) NSA. NO. R-4 - 12" mix. 6" ove

6. FILTER STONE NO. FS-2



Rip-Rap Apron Summary										
	Pipe 25-year Initial Apron Apron									
Headwall	Diameter,	25-year	Velocity	Rip-Rap	Apron	Length,	Width,			
ID	D0 (in)	Q (cfs)	(ft/sec) Size d50		width (ft)	La (ft)	W (ft)			
100	18	0.6	4.2	0.5	4.5	9	10.5			


RIP RAP NOT TO SCALE




TREE SAVE FENCE DETAIL
ONT TO SCALE

TYPE OF SPECIES YEAR EQUIVALENT N.P.K		RATE	TOP DRESSING RATE	
Cool season	Firet	6-12-12	1500 bs./ac.	50-100 bs./ac. 1/2
grasses	Second	6-12-12	1000 lbs./ac.	30
	Maintenance	10 10 10	400 lbs./sc.	30
2. Cool season	First	6.12.12	1500 bs./sc.	0.50 fbs./ws. 1/
crasses and	Second	0.10-10	1000 Brs./ec.	
leggmen.	Mantenance	0.10-10	400 bs./sr	
1000000000	4949770411441111		-0.000000000000000000000000000000000000	_
 Ground extrems 	First	10-10-10	1300 Bs./ac.3/	_
	Second	10-10-10	1300 lbs./ec. 3/	=
	Maintenance	10-10-10	1100 bs/ac.	-
Pine seedlings	First	20-10-5	one 21 gram pellet	_
			per seeding placed	
			in the closing hole	
5. Shoub Lespedaza	First	0-10-10	700 he oc	
	Maintenance	0-10-10	700 lbs/ac.4/	_
6. Tomporary	First	10-10-10	500 be.rsc.	30 lbs.4sc.5/
cover crops				
seeded alone				
7 Warm spason	First	8.12.12	1600 he (ac	60-100 be inc 2:6
grasses	Second	6 12 12	800 lbs/lsc.	50-100 bs /ac. 2/
	Maintenance	10 10 10	400 tos./sc.	30 bs/sc.
8. Warm season	First	6.12.12	1500 be/ac.	50 lbs /ac /6/
cosses and	Second	0:10:10	1000 be/sc	
legumes	Maintenance	D-10-10	400 by inc	

FERTILIZER APPLICATION TABLE $\left(\begin{array}{c}2\\C-8\end{array}\right)$ NOT TO SCALE






SIGNATURE OF ENGINEER 1575 CERTIFICATION #

Foresite Group, Inc. 5185 Peachtree Pkwy. Suite 240 Norcross, GA 30092 o | 770.368.1399 f | 770.368.1944 w | www.fg-inc.net

DEVELOPER:

CONTACT:

BROOK RUN DOG PARK **DESIGN DEVELOPMENT**



DATE REVISIONS

PROJECT MANAGER: JVW NJP DRAWING BY: JURISDICTION: DUNWOODY, GA 9 AUGUST 2013 SCALE: AS SHOWN TITLE:

EROSION CONTROL DETAILS

SHEET NUMBER:

11/4/13

DATE 04/22/2014 EXPIRATION

C-8

COMMENTS: NOT RELEASED FOR CONSTRUCTION

JOB/FILE NUMBER:

(Ds2) DISTURBED AREA STABILIZATION (WITH TEMPORARY SEEDING)

PLANTS, PLANTING RATES AND PLANTING DATES FOR TEMPORARY COVER OR COMPANION CROPS

		OR CO	I PAI	VIOI-		NOI									
SPECIES	BROADCAST RATES 1/ - PLS 2/ PER PER ACRE 1000 SQ. FT.	RESOURCE AREA 3/	PLANTING DATES BY RESOURCE AREAS PLANTING DATES (SOLID LINES INDICATE OPTIMUM DATES OOTTED LINES INDICATE PERMISSIBLE BUT OPTIONAL DATES)						ICE IUM VISS	DAT IBLE	AS ES BUT		REMARKS		
			Г	F	м	Α	w	J	T 4	s	١.	N	D		
BARLEY (HORDEUM VULGARE) ALONE IN MIXTURES	3 BU. (144 LBS.) 3.3 LB 1/2 BU. (24 LBS.) 0.6 LB	M-L P C							-	F	F	Ė			14,000 DEED PER POUND. WINTER HARDY USE ONLY ON PRODUCTIVE SOILS.
	(21 200) 0.0 20		-	F	м	A	м	J	^	s	۰	N	D		
LESPEDEZA, ANNUAL (LEZPEDEZA STRIADA) ALONE	40 LBS 0.9 LB	M-L P C		F											200,000 SEED PER POUND. MAY VOLUNTEER FOR SEVERAL YEARS. USE MOCULATE EL.
IN MIXTURES	10 LBS 0.2 LB		-	F	м	A	w	J	ļ,	s	0	N	D		
LOVEGRASS, WEEPING (ERAGROSTIS BURVULA)		W -L P	T	Ĺ	=			Ŧ			Ī				1,500,000 SEED PER POUND. MAY LAST SEVERAL YEARS. MIX WITH SERICEA LESPEDEZA.
ALONE IN MIXTURES	4 LBS 0.1 LB 2 LBS 0.5 LB	С		F	м	A	u	J		s	0	N	D		
MILET, BROWNTOP (PANICUM FASCICULATUM)		M-L P	T	T		1		#	İ		l				137,000 SEED PER POUND. QUICK DENSE COVER. WILL PROVIDE TOO COMPETITION IN MIXTURES IF SEEDED AT HIGH RATE.
ALONE IN MIXTURES	40 LBS 0.9 LB 10 LBS 0.2 LB	С	-	F	w	A	u	J	A	s	0	N	D		AT HIGH RATE.
MILLET, PEARL (PENNESETUM GLAUCUM)		M-L P C	T	T		Ī		Ī	Ī	Ī	Ī				88,000 SEED PER POUND. QUICK DENSE COVER. MAY REACH 5 FEET IN HEIGHT. NOT RECOMMENDED FOR
ALONE IN MIXTURES	50 LBS 1.1 LB			F	w	A	u	J	^	s	0	N	D		MIXTURES.
OATS (AVENA SATIVA) ALONE	4 BU. (128 LBS.) 2.9 LB 1 BU.	W -L P						Ī	Ī	E	F	Ē			13,000 SEED PER POUND. USE ON PRODUCTIVE SOLS. NOT AS WINTERHARDLY AS RYE OR BARLEY.
IN MIXTURES	1 BU, (32 LBS.) 0.7 LB	-		F	м	A	u	J	A	s	0	N	D		
RYE (SECALE CEREALE) ALONE IN MIXTURES	3 BU. (168 LBS.) 3.9 LB 1/2 BU. (28 LBS.) 0.6 LB	M-L P C							-	F	F				18,000 SEED PER POUND, QUICK COVER, DROUGHT TOLERANT AND WN TERHARDY.
	(20 102) 40 10		1	F	м	A	w	J	^	s	0	N	D		
RYEGRASS ANNUAL (LOLIUM TEMULENTUM)		W-L P	T					T	E	Ē	E				227,000 SEED PER LB. DENSE COVER. VERY COMPETITIVE AND IS NOT TO BE USED IN MIXTURES.
ALONE	40 LBS 0.9 LB	٠	-	F	м	A	u	JJ	A	s	0	N	D		
SUDANGRASS (SORGHUM SUDANESE)		W -L P C							F						55,000 SEED PER LB. GOOD ON DROUGHT SITES AND IS NOT TO BE USED IN MIXTURES.
ALONE	60 LBS 1.4 LB	•		F	м	A	u	J	_	s	0	N	D		out in minimital.
TRITICALE (X-TRITICOSECALE) ALONE IN MIXTURES	3 BU. (144 LBS.) 3.3 LB 1/2 BU. (24 LBS.) 0.6 LB	c	Ī							Ī					USE ON LOWER PART OF SOUTHERN COASTAL PLAIN AND IN ATLANTIC COASTAL FLATNOODS ONLY.
			J	F	м	A	м	J	A	s	٥	N	D		
WHEAT (TRITICUM AESTIVUM) ALONE IN MIXTURES	3 BU. (180 LBS.) 4,1 LB 1/2 BU. (30 LBS.) 0.7 LB	M-L P C	F	-							F	F			15,000 SEED PER POUND. WINTERHARDY

I/ TEUROPARY COVER CROPS ARE VERY COMPETITIVE AND WILL CROWN OUT PERDINALS IF SECRED TOO HEAVILY.

// REDUCE SECONG MATES BY DON MEN DIMLED.

// REDUCES SECONG MATES BY DON MEN DIMLED.

// WILL COMPETED SECRED FOR DONE OF THE SECONG AND VALLEYS MUPS'S

PROPERSON'S THE SOUTHERN PERSON'S MURA SHAD MILLS: BLOCK MILLS: BLOCK LANDS; AND ATLANTIC COASTAL FLATINGOOS MURA'S

COMPETED SOUTHERN COASTAL FALM, SHAD MILLS: BLOCK MILLS: BLOCK LANDS; AND ATLANTIC COASTAL FLATINGOOS MURA'S

DS1 DISTURBED AREA STABILIZATION (WITH MULCHING ONLY)

MULCIAING WINGLE SEEDING
THIS STRUNGED APRIES TO GRADES OR CLEARED AREAS WHERE SEEDINGS MAY NOT
HAVE A SUITABLE GROWING SEASON TO PRODUCE AN EROSION RETARDANT COVER, BUT CAN BE
ESTABLISHED WITH A MULCH COVER.

SITE PREPARATION

1. GRADE TO PERMIT THE USE OF EQUIPMENT FOR APPLYING AND ANCHORNO MULCH.

2. HISTALL NEEDED EROSON CONTROL MEASURES AS REQUIRED SUCH AS DIKES, DIVERSIONS
BERMS, TERRACES AND SEDIMENT BARBERS.

2. LOSSEN CORPACT SOLIT OR A MINIORING DEPT OF 3 INCHES.

 $\frac{\textit{MULCHING MATERIALS}}{\textit{SELECT ONE OF THE FOLLOWING MATERIALS AND APPLY AT THE DEPTH INDICATED:}$

SELECT ONE OF THE FELLOWING WATERIALS AND APPLY AT THE OPETH MOCKETOR.

DIFF STRANG OF HAT SHALL ELE APPLED AT THE OPETH AS TO THE APPLYONGE

CONTROL OF THE SHALL
APPLYING MULCH IS USED WITHOUT SEEDING, MULCH SHALL BE APPLIED TO PROVIDE FULL COVERAGE OF THE EXPOSED AREA.

COVERACE OF THE EMPOSED MARK.

1. DRY STRAWS ON AHM MIGCH AND WOOD CHIPS SHALL BE APPLIED UNFORMLY BY HAND OR

2. IF HE AREA, MILL (SVITHALLY SE COURSED WITH PERDMALL VECETION, 20–50 POUNDS
OF WITHOUT SERVICE AND AND DET

A. APLY POLYTHYLER FLU OI LOPGED MACE.

A PROVIDENCE MACE VALUE OF THE STORY WITH A DOR HARBOW WITH THE DORSEST OF THE STORY WAS A STORY OF THE STOR

MANUFACTURERYS SPICOPICATIONS.

3. NETTING OF THE APPROPRIATE SIZE SHALL BE USED TO AMORR ROOD WASTE OPENINGS OF THE NETTING SHALL NOT BE LARGER THAN THE AVERAGE SIZE OF THE WOOD WASTE CHIPS.

4. POLYETHYLENE FILM SHALL BE ANCHOR TRENCHED AT THE TOP AS WELL AS NICESSENTIALLY AS NICESSENTIALY TO NICESSENTIALY TO NICESSENTIALY TO NICESSENTIALY TO NICESSENTIALY.

MULCH IS REQUIRED FOR ALL PERMANENT VEGETATION APPLICATIONS. MULCH APPLIED TO SEEDED AREAS SHALL ACHIEVE 75% SOIL COVER. DRY STRAW OF DRY HAY OF GOOD QUALITY AND FREE OF WEED SEEDS CAN BE USED. DRY STRAW SHALL BE APPLED AT THE RATE OF 2 TONS PER ACRE. DRY HAY SHALL BE APPLED AT A RATE OF 1 1/2 TONS PER ACRE.

APPLYING MALCH
STRAW OR HAY MALCH SHALL BE SPREAD UNFORMLY WITHIN 24 HOURS AFTER SEEDING
AMO/OR PLANTING. THE MULCH MAY BE SPREAD BY BLOKER—TYPE SPREADING EQUIPMENT,
OTHER SPREADING EQUIPMENT OR BY HAND. MULCH SHALL BE APPLIED TO COVER 75% OF
THE SOL SURFACE.

THE SULL SWITTERS STATEMENT OF THE STATEMENT WHITE THE MULCH IS STRANG HAVE MALCH SHALL BE PRESSED INTO THE SOIL MANEDIATELY AFTER THE MULCH IS SPREAD, A SPECIAL PACKER DISK OR DOS HARROW WITH THE DISKS SET STRAIGHT MAY BY SPREAD, A SPECIAL STRAIGHT MAY BY DIAMETER AND 8 TO 12 KNOTES APART. THE EDISKS OF THE DISKS SHALL BE DULL DROUGH TO PRESS THE MULCH AND THE MEDICAL WHITHOUT THE LEAVING MUCH OF IT IN AN ERECT POSITION. MULCH SHALL NOT BE FLORED INTO THE SOIL.

DS3 DISTURBED AREA STABILIZATION (WITH PERMANENT VEGETATION)

FERTILIZER REQUIREMENTS

TYPES OF SPECIES	YEAR	ANALYSIS OR EQUIVALENT N-P-K	RATE	TOP DRESSING RATE
1. COOL SEASON GRASSES	FIRST SECOND MAINTENANCE	6-12-12 6-12-12 10-10-10	1500 LBS./AC 1000 LBS./AC 400 LBS./AC	50-100 LBS/AC 1/2/ 30
2. COOL SEASON GRASSES AND LEGUMES	FIRST SECOND MAINTENANCE	6-12-12 0-10-10 0-10-10	1500 LBS./AC 1000 LBS./AC 400 LBS./AC	0-50 LBS/AC 1/
3. GRAOUD COVERS	FIRST SECOND MAINTENANCE	10-10-10 10-10-10 10-10-10	1300 LBS./AC 3/ 1300 LBS./AC 3/ 1100 LBS./AC	==
4. PINE SEEDLINGS	FIRST	20-10-15	ONE 21-GRAM PELLET PER SEEDLING PLACED IN THE CLOSING HOLE	
5. SHRUB LESPEDEZA	FIRST MAINTENANCE	0-10-10 0-10-10	700 LBS./AC 700 LBS./AC 4/	
6. TEMPORARY COVER CROPS SEEDED ALONE	FIRST	10-10-10	500 LBS./AC	30 LBS/AC 5/
7. WARM SEASON GRASSES	FIRST SECOND MAINTENANCE	6-12-12 6-12-12 10-10-10	1500 LBS./AC 800 LBS./AC 400 LBS./AC	50-100 LBS/AC 2/6/ 50-100 LBS/AC 2/ 30 LBS/AC
B. WARM SEASON CRASSES AND LEGUMES	FIRST SECOND MAINTENANCE	6-12-12 0-10-10 0-10-10	1500 LBS./AC 1000 LBS./AC 400 LBS./AC	50-100 LBS/AC 6/

1/ APPLY IN THE SPRING FOLLOWING SEEDING.
2/ APPLY IN SPILT APPLICATIONS WHEN HIGH RATES ARE USED.
3/ APPLY IN SPILT APPLICATIONS.
4/ APPLY WHEN PLANTS ARE PRUNED.
5/ APPLY TO GRASS SPECES ONLY.
6/ APPLY WHEN PLANTS GROW TO HEIGHT OF 2 TO 4 INCHES.

IME AND FERTILIZER RATES AND ANALYSIS

AGRICULTURAL LIME IS REQUIRED AT THE RATE OF ONE TO TWO TONS PER ACRE UNLESS SOIL TEST INDICATE OTHERWISE. CRADED AREAS REQUIRE LIME APPLICATION. IF LIME IS APPLIED WHITHIN SIX MONTHS OF PLANTING PERMANENT PERENNIAL VICETAINAL, ADDITIONAL LIME IS NOT REQUIRED. AGRICULTURAL LIME SHALL BE WITHIN THE SPECIFICATION OF THE FLORIDA DEPARTMENT OF AGRICULTURAL

LIME SPEED OF CONSENSIONAL EQUIPMENT SHALL BE "CROWN DIMESTONE". CROWN DIMESTONE SCALE OF BOOK OF THE METERAL WILL STOKE CROWN DIMESTONE SCALE OF BOOK OF THE MATERIAL WILL SHALL BE SHALL BOOK OF THE MATERIAL WILL SHALL BOOK OF THE MATERIAL BOOK OF






TO BE SHOWN ON THE EROSION AND SEDIMENT CONTROL PLAN If the EXCAYATED INLET SEDIMENT TRAP is used, show the following info

ons: l = 30 ft w = 25 ft diameter (** applicable) = N/A ft

STORAGE PROVIDED = 56 CY Provide a detail showing the depth, length and width, or diameter (*/app@able), and side slopes of the excavation.

EXCAVATED Sd2-F #1 CALCULATION



1. FOR STAKES, USE STEEL WITH A MINIMUM LENGTH OF 3 FEET.


2. SPACE STAKES EVENLY AROUND THE PERIMETER OF THE INLET A MAXIMUM OF 3 FEET APART, AND SECURELY DRIVE THEM INTO THE GROUND, MINIMUM OF 18 INCHES DEEP.


3. TO PROVIDE NEEDED STABILITY TO THE INSTALLATION, FRAME WITH 2 \times 4 INCH WOOD STRIPS AROUND THE CREST OF THE OVERFLOW AREA AT A MAXIMUM OF 1.5 FEET ABOVE THE DROP INLET CREST.

4. PLACE THE BOTTOM 12 INCHES OF THE FABRIC IN A TRENCH AND BACKFILL THE TRENCH WITH CRUSHED STONE OF COMPACTED SOIL.

5. FASTEN FABRIC SECURELY TO THE STAKES AND FRAME. JOINTS MUST BE OVERLAPPED TO THE NEXT STAKE. 6. THE TOP OF THE FRAME AND FABRIC MUST BE WELL BELOW THE GROUND ELEVATION DOWNSLOPE FROM THE DRO INLET TO KEEP RUNOFF FROM BYPASSING THE INLET. IT MAY BE NECESSARY TO BUILD A TEMPORARY DIKE ON THE DOWN SLOPE SIDE OF THE STRUCTURE TO PREVENT BYPASS FLOW.

SEDIMENT TRAP (Sd2-F)





COMPOST FILTER SOCK



Sd1-CFS COMPOST FILTER SOCK NOT TO SCALE

TO BE SHOWN ON THE EROSION AND SEDIMENT CONTROL PLAN

if the EXCAVATED INLET SEDIMENT TRAP is used, show the following infor

1. Drainage area = 0.16 ac

2. Required sediment storage = 67 cylac * drainage area
Required sediment storage = 67 cylac * 0.16 ac
Required sediment storage = 67 cylac * 0.16 ac
Required sediment storage = 10.7 cy = 717 of

3. Assume excavation depth (inimium of 1.5 ft.) = 4 ft.
Assume excavation depth (inimium of 1.5 ft.) = 4 ft.

3. Assume excavation depth (inimium of 1.5 ft.) = 4 ft.

3. Assume singe of eldee (final into the steeper han 2.1) = 1

3. Assume singer of y / 4 ft.

3. Assume shape of excavation and determine dimensions.

4. Arectangular shape with 2.1 length to width ratio is recommended.)

Shape: SOUARE

Shape: SOURE

Dimensions: I = 12 ft w = 12 ft diameter (# applicable) = N/A ft

STORAGE PROVIDED = 7 CY Provide a detail **showing the depth,** length and width, or dia**meter (# applicable)**, and side slopes of the exc**avation**.

EXCAVATED Sd2-F #2 CALCULATION

TO BE SHOWN ON THE EROSION AND SEDIMENT CONTROL PLAN

If the EXCAVATED INLET SEDIMENT TRAP is used, show the following inform

1. Drainage area = 0.79 ac
2. Required sediment storage = 67 cylac * drainage area
Required sediment storage = 67 cylac * 0.79 ac
Required sediment storage = 50 cylac * 0.79 ac
Required sediment storage = 53 cy = 1431 of
1. Assume excavation depth (minimum of 1.5 ft.) = 2
1. Assume excavation depth (minimum of 1.5 ft.) = 2
2.1 Determine required surface area
SA. — Boddend average = 1.5 cylac * 1.5

Provide a detail **showing the depth**, length and width, or diameter (# eppticable), and side slopes of the excevation. STORAGE PROVIDED = 64 CY

EXCAVATED Sd2-F #3 CALCULATION

EXCAVATED INLET SEDIMENT TRAP CALCULATIONS

	Rt Calculations	
Disturbed A	rea Draining to Pond (acres):	1.30
1. Required	Stormwater Storage (C.Y.):	0
2. Required	Sediment Storage (C.Y.):	87
3. Total rec	uired storage (C.Y.) = 1+2 :	87
4. Avaliable	Storage (C.Y.):	50
5. Is the av	aliable storage (4) greater	
than the	total required storage (3)?	NO
6. lf "no", t	he sidement storage capacity	
of the po	and must be increased. Choose	
the meth	od to be used:	
	Raise Inv. Of outlet structure	
	Undercut the pond	
	Other	
7. Clean-ou	t elevation:	981.8
8. Is the ler	gth-width ratio 2:1 or greater?	Yes
9. lf "no", t	he length of flow must be increased.	
Choose met	hod to be used:	
	Baffles	
	Other	
Dia. and He	ight of half-round CMP retrofit to be u	used:
	Diameter (in)	30
	Height (ft)	4

RETROFIT CALCULATIONS

NGINEER

Foresite Group, Inc. 5185 Peachtree Pkwy. f | 770.368.1944 Norcross, GA 30092 w | www.fg-inc.net

DEVELOPER:

CONTACT:

PARK

ROOK RUN DOG

 $\overline{\mathbf{m}}$

DESIGN DEVELOPMENT . RD. , GEO' RICT 4770 N. PEACHTREE R PY, DEKALB COUNTY, GI L.L. 354, 18TH DISTRIC



DATE REVISIONS

PROJECT MANAGER:	JVW
DRAWING BY:	NJF
JURISDICTION:	DUNWOODY, GA
DATE:	9 AUGUST 2013
SCALE:	AS SHOWN
TITLE:	

EROSION CONTROL DETAILS

SHEET NUMBER:

C-8.1

COMMENTS:

NOT RELEASED FOR CONSTRUCTION JOB/FILE NUMBER:

