

ITB 18-03 BID SCHEDULE**Addendum #1, 8/15/2018****PROJECT: North Peachtree Road at I-285 Ramp Planting****Bids Due: September 11, 2018**

| Item # | Item Description | QTY | U/M | Unit Rate | Extended AMT | Comments |
|--------|---|------|-----|-----------|--------------|------------|
| | Traffic Control | 1 | LS | | | |
| | Tree removal and disposal, selective clearing | 1 | LS | | | |
| | Tree Protection | 121 | LF | | | |
| | Grading / Site Demolition | 1 | LS | | | See Note 1 |
| | Fine grading for new sod and plant beds | 1 | LS | | | See Note 2 |
| | Silt Fence / Erosion Control (incl. maint.) | 1120 | LF | | | |
| | #7 'Cherry Dazzle' Crape Myrtle | 33 | EA | | | |
| | #5 Inkberry 'Shamrock' | 58 | EA | | | |
| | #3 Beautyberry | 7 | EA | | | |
| | #3 'Mrs. Schiller's Delight' Viburnum | 28 | EA | | | |
| | #3 'Henry's Garnet' Sweetspire | 20 | EA | | | |
| | #5 'Sugar Shack' Button Bush | 1 | EA | | | |
| | #1 Cardinal Flower | 24 | EA | | | |
| | #1 'Shenandoah' Switchgrass | 68 | EA | | | |

| Item # | Item Description | QTY | U/M | Unit Rate | Extended AMT | Comments |
|--------|--|--------|------|-----------|--------------|-------------------------------------|
| | #1 Pink Muhly Grass | 115 | EA | | | |
| | #1 'Rose Creek' Abelia | 74 | EA | | | |
| | Hand-placed River Rounds, Rock | 6 | TONS | | | |
| | Rain Garden | 2 | ea | | | |
| | Turf Reinf. matting for Rain Garden - Type 1 | 250 | SYD | | | GDOT QPL |
| | Bermuda Sod (Tiftway '419' or equal) | 20,000 | SF | | | |
| | Hardwood Mulch | | CYDs | | | 2-3 inches compacted at all LS beds |
| | Watering (3 months) | 3 | MO | | | |
| | | | | | \$ | TOTAL BID |

BID NOTES:

Grading / Site Demolition shall include the following: removal /disposal of concrete flume/concrete pedestal;

Note 1: import fill for flume replacement, sawcutting, dumpsters; includes all scope per "Flume Removal and Notes Plan"

Fine grading for new sod and plant beds shall include the following: trench edges at all planter beds, rock rake all sod areas,

NOTE 2: soil amendments as specified, hand digging where specified; 1-inch top dressing prior to placing sod

Submitted by:

Contractor

Date