

4800 Ashford Dunwoody Road Dunwoody, Georgia 30338 dunwoodyga.gov | 678.382.6700

MEMORANDUM

To: Mayor and City Council

From: Cody Dallas, Senior Stormwater Engineer

Date: March 10, 2025

Subject: Funding Authorization for 1421 Mockwell Court Storm

Repairs

ACTION

Authorize the Mayor, City Manager, or designee to allocate up to \$158,677.07 through its unitprice contract with Southern Premier Contractors to complete stormwater pipe repairs at 1421 Mockwell Court.

SUMMARY

Structural deficiencies to the storm system and sanitary sewer main at 1421 Mockwell Court caused a sinkhole to form at the project location. The storm system is composed of an 18-inch corrugated metal pipe (CMP) pipe measuring +/-160 linear feet. A sinkhole has formed approximately 115 linear feet downstream of the catch basin at the roadway. The final 45 linear feet of pipe is bent into the sinkhole from the weight of surface material. The original headwall elevation is perched above the stream. The system is approximately 49 years old and in poor condition. Closed-Caption Television (CCTV) footage found corrosion and minor deformation in the intact portion of the pipe system.

Recommended repairs include:

- Remove existing headwall and +/- 45 LF of failed CMP
- Install new junction box with surface level access
- Install +/- 40 LF of 18-inch RCP
- Install new headwall and erosion protection measures at end of new 18-inch RCP
- Repair +/-115 LF of 18-inch CMP with CIPP
- Replace driveway of 1416 Mockwell Court being used for access during project


If approved by Council, this project will be funded from the Stormwater Utility's annual repairs and maintenance budget.

RECOMMENDED ACTION

Authorize the Mayor, City Manager, or designee to allocate up to \$158,677.07 through its unitprice contract with Southern Premier Contractors to complete stormwater pipe repairs at 1421 Mockwell Court.



Project Map







Estimate

Date	Estimate #
2/21/2025	229099

Name / Address

CITY OF DUNWOODY 4800 ASHFORD DUNWOODY DUNWOODY, GA 30338

Project	
1421 MOCKWELL CT	

DN001	Item	Qty	Description	Rate	Amount
DN002 4 OUT OF SCOPE WORK, FOREMAN 104,88 706.56	DN001	1	MOBILIZATION	2,208.05	2,208.05
DN003					
DN005					706,56
DN008		6			
DN013			AND SIGNAGE	,	,
DN013	DN008	115	TV STORM LINES (INCLUDES DIGITAL FILE &	4.42	508.30
DN048			REPORT)		
DN059	DN013	115	18" PIPE - CLEANING LESS THAN 25% FULL	6.46	742.90
DN101	DN048	40	18" SRCMP	77.28	3,091.20
DN128	DN059	40	18" RCP	88.32	3,532.80
DN176	DN101	1	PRECAST HEADWALL FOR 18" PIPE	1,048.82	1,048.82
DN206	DN128	8	18" DIAMETER INTERNAL PIPE POINT REPAIR	662.42	5,299.36
DN206 2 INVERT INSTALLATION, 4' DIAMETER 496.81 993.62 DN220 4 18" GROUT EACH END TO STRUCTURE 215.28 861.12 DN305 115 18" PIPE - 9.0 MM (.354") CIPP 160.16 18,418.40 DN3381 1 INVERSION SETUP CHARGE 15"-36" CIPP 2,760.06 2,760.06 DN335 150 DRIVEWAY 6" CONCRETE (COMMERCIAL w/6" OF GAB INCLUDED) GAB INCLUDED) DN361 2 TREE REMOVAL 13"-23" 1,987.25 3,974.50 DN362 1 TREE REMOVAL 223" 3,532.88 3,532.88 DN363 125 CLEAR & GRUBBING 16.56 2,070.00 DN365 102 ADDITIONAL EXCAVATION 22.08 2,252.16 DN366 102 ADDITIONAL EXCAVATION 22.08 2,252.16 DN367 102 HAUL-IN STRUCTURAL FILL MATERIAL 82.80 8,445.60 DN367 102 HAUL-OFF SOIL MATERIAL 93.84 9,571.68 DN368 275 FINISH GRADING 11.04 3,036.00 DN372 36 STONE RIP RAP TYPE III IN PLACE 104.88 3,775.68 DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - 8.83 441.50 ALTERNATIVE	DN176	12	4' ROUND PRECAST INLET w/PEDESTAL TOP &	883.22	10,598.64
DN220 4 18" GROUT EACH END TO STRUCTURE 215.28 861.12 DN305 115 18" PIPE - 9.0 MM (.354") CIPP 160.16 18,418.40 DN3381 1 INVERSION SETUP CHARGE 15"-36" CIPP 2,760.06 2,760.06 DN335 150 DRIVEWAY 6" CONCRETE (COMMERCIAL w/6" OF GAB INCLUDED) 104.88 15,732.00 DN361 2 TREE REMOVAL 13"-23" 1,987.25 3,974.50 DN362 1 TREE REMOVAL >23" 3,532.88 3,532.88 DN363 125 CLEAR & GRUBBING 16.56 2,070.00 DN365 102 ADDITIONAL EXCAVATION 22.08 2,252.16 DN366 102 HAUL-IN STRUCTURAL FILL MATERIAL 82.80 8,445.60 DN367 102 HAUL-OFF SOIL MATERIAL 93.84 9,571.68 DN372 36 STONE RIP RAP TYPE III IN PLACE 104.88 3,775.68 DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - ALTERNATIVE 8.83 441.50 DN380 100 INSTALL & REMOVE ORANGE TREE SAVE FENCE 11.			GRATE OR MH RING & COVER		
DN305 115 18" PIPE - 9.0 MM (.354") CIPP 160.16 18,418.40 DN3381 1 INVERSION SETUP CHARGE 15"-36" CIPP 2,760.06 2,760.06 DN335 150 DRIVEWAY 6" CONCRETE (COMMERCIAL w/6" OF GAB INCLUDED) 104.88 15,732.00 DN361 2 TREE REMOVAL 13"-23" 1,987.25 3,974.50 DN362 1 TREE REMOVAL >23" 3,532.88 3,532.88 DN363 125 CLEAR & GRUBBING 16.56 2,070.00 DN365 102 ADDITIONAL EXCAVATION 22.08 2,252.16 DN366 102 HAUL-IN STRUCTURAL FILL MATERIAL 82.80 8,445.60 DN367 102 HAUL-OFF SOIL MATERIAL 93.84 9,571.68 DN372 36 STONE RIP RAP TYPE III IN PLACE 104.88 3,775.68 DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - ALTERNATIVE 8.83 441.50 DN380 100 INSTALL & REMOVE ORANGE TREE SAVE FENCE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 16.56 </td <td>DN206</td> <td>2</td> <td>INVERT INSTALLATION, 4' DIAMETER</td> <td>496.81</td> <td>993.62</td>	DN206	2	INVERT INSTALLATION, 4' DIAMETER	496.81	993.62
DN3381 1 INVERSION SETUP CHARGE 15"-36" CIPP 2,760.06 2,760.06 DN335 150 DRIVEWAY 6" CONCRETE (COMMERCIAL w/6" OF GAB INCLUDED) 104.88 15,732.00 DN361 2 TREE REMOVAL 13"-23" 1,987.25 3,974.50 DN362 1 TREE REMOVAL >23" 3,532.88 3,532.88 DN363 125 CLEAR & GRUBBING 16.56 2,070.00 DN365 102 ADDITIONAL EXCAVATION 22.08 2,252.16 DN366 102 HAUL-IN STRUCTURAL FILL MATERIAL 82.80 8,445.60 DN367 102 HAUL-OFF SOIL MATERIAL 93.84 9,571.68 DN368 275 FINISH GRADING 11.04 3,036.00 DN372 36 STONE RIP RAP TYPE III IN PLACE 104.88 3,775.68 DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - ALTERNATIVE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 11.04 1,104.00 DN391 40 PINE STRAW 9.94 397.60 <tr< td=""><td>DN220</td><td>4</td><td>18" GROUT EACH END TO STRUCTURE</td><td>215.28</td><td>861.12</td></tr<>	DN220	4	18" GROUT EACH END TO STRUCTURE	215.28	861.12
DN335	DN305	115	18" PIPE - 9.0 MM (.354") CIPP	160.16	18,418.40
DN361	DN3381	1	INVERSION SETUP CHARGE 15"-36" CIPP	2,760.06	2,760.06
DN361 2 TREE REMOVAL 13"-23" 1,987.25 3,974.50 DN362 1 TREE REMOVAL >23" 3,532.88 3,532.88 DN363 125 CLEAR & GRUBBING 16.56 2,070.00 DN365 102 ADDITIONAL EXCAVATION 22.08 2,252.16 DN366 102 HAUL-IN STRUCTURAL FILL MATERIAL 82.80 8,445.60 DN367 102 HAUL-OFF SOIL MATERIAL 93.84 9,571.68 DN368 275 FINISH GRADING 11.04 3,036.00 DN372 36 STONE RIP RAP TYPE III IN PLACE 104.88 3,775.68 DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - ALTERNATIVE 8.83 441.50 DN380 100 INSTALL & REMOVE ORANGE TREE SAVE FENCE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 16.56 2,782.08 DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN335	150	DRIVEWAY 6" CONCRETE (COMMERCIAL w/6" OF	104.88	15,732.00
DN362 1 TREE REMOVAL >23" 3,532.88 3,532.88 DN363 125 CLEAR & GRUBBING 16.56 2,070.00 DN365 102 ADDITIONAL EXCAVATION 22.08 2,252.16 DN366 102 HAUL-IN STRUCTURAL FILL MATERIAL 82.80 8,445.60 DN367 102 HAUL-OFF SOIL MATERIAL 93.84 9,571.68 DN368 275 FINISH GRADING 11.04 3,036.00 DN372 36 STONE RIP RAP TYPE III IN PLACE 104.88 3,775.68 DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - 8.83 441.50 DN380 100 INSTALL & REMOVE ORANGE TREE SAVE FENCE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 16.56 2,782.08 DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06			GAB INCLUDED)		
DN363 125 CLEAR & GRUBBING 16.56 2,070.00 DN365 102 ADDITIONAL EXCAVATION 22.08 2,252.16 DN366 102 HAUL-IN STRUCTURAL FILL MATERIAL 82.80 8,445.60 DN367 102 HAUL-OFF SOIL MATERIAL 93.84 9,571.68 DN368 275 FINISH GRADING 11.04 3,036.00 DN372 36 STONE RIP RAP TYPE III IN PLACE 104.88 3,775.68 DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - ALTERNATIVE 8.83 441.50 DN380 100 INSTALL & REMOVE ORANGE TREE SAVE FENCE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 16.56 2,782.08 DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN361	2	TREE REMOVAL 13"-23"	1,987.25	3,974.50
DN365 102 ADDITIONAL EXCAVATION 22.08 2,252.16 DN366 102 HAUL-IN STRUCTURAL FILL MATERIAL 82.80 8,445.60 DN367 102 HAUL-OFF SOIL MATERIAL 93.84 9,571.68 DN368 275 FINISH GRADING 11.04 3,036.00 DN372 36 STONE RIP RAP TYPE III IN PLACE 104.88 3,775.68 DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - ALTERNATIVE 8.83 441.50 DN380 100 INSTALL & REMOVE ORANGE TREE SAVE FENCE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 16.56 2,782.08 DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN362	1	TREE REMOVAL >23"	3,532.88	3,532.88
DN366 102 HAUL-IN STRUCTURAL FILL MATERIAL 82.80 8,445.60 DN367 102 HAUL-OFF SOIL MATERIAL 93.84 9,571.68 DN368 275 FINISH GRADING 11.04 3,036.00 DN372 36 STONE RIP RAP TYPE III IN PLACE 104.88 3,775.68 DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - 8.83 441.50 ALTERNATIVE NSTALL & REMOVE ORANGE TREE SAVE FENCE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 16.56 2,782.08 DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN363	125	CLEAR & GRUBBING	16.56	2,070.00
DN367 102 HAUL-OFF SOIL MATERIAL 93.84 9,571.68 DN368 275 FINISH GRADING 11.04 3,036.00 DN372 36 STONE RIP RAP TYPE III IN PLACE 104.88 3,775.68 DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - ALTERNATIVE 8.83 441.50 DN380 100 INSTALL & REMOVE ORANGE TREE SAVE FENCE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 16.56 2,782.08 DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN365	102	ADDITIONAL EXCAVATION	22.08	2,252.16
DN368 275 FINISH GRADING 11.04 3,036.00 DN372 36 STONE RIP RAP TYPE III IN PLACE 104.88 3,775.68 DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - ALTERNATIVE 8.83 441.50 DN380 100 INSTALL & REMOVE ORANGE TREE SAVE FENCE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 16.56 2,782.08 DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN366	102	HAUL-IN STRUCTURAL FILL MATERIAL	82.80	8,445.60
DN372 36 STONE RIP RAP TYPE III IN PLACE 104.88 3,775.68 DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - ALTERNATIVE 8.83 441.50 DN380 100 INSTALL & REMOVE ORANGE TREE SAVE FENCE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 16.56 2,782.08 DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN367	102	HAUL-OFF SOIL MATERIAL	93.84	9,571.68
DN377 50 INSTALL & REMOVE TYPE C SILT FENCE - ALTERNATIVE 8.83 441.50 DN380 100 INSTALL & REMOVE ORANGE TREE SAVE FENCE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 16.56 2,782.08 DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN368	275	FINISH GRADING	-	3,036.00
DN380 100 INSTALL & REMOVE ORANGE TREE SAVE FENCE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 16.56 2,782.08 DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN372			104.88	3,775.68
DN380 100 INSTALL & REMOVE ORANGE TREE SAVE FENCE 11.04 1,104.00 DN386 168 SODDING COMPLETE - FESCUE 16.56 2,782.08 DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN377	50	INSTALL & REMOVE TYPE C SILT FENCE -	8.83	441.50
DN386 168 SODDING COMPLETE - FESCUE 16.56 2,782.08 DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06			ALTERNATIVE		
DN391 40 PINE STRAW 9.94 397.60 DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN380	100	INSTALL & REMOVE ORANGE TREE SAVE FENCE		
DN407 10 DEBRIS REMOVAL, TANDEM DUMP TRUCK 938.42 9,384.20 DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN386	168	SODDING COMPLETE - FESCUE		2,782.08
DN408 1 REMOVAL OF EXISTING NON-DRAINAGE 2,760.06 2,760.06	DN391	40	PINE STRAW	9.94	397.60
	DN407	10	DEBRIS REMOVAL, TANDEM DUMP TRUCK		9,384.20
STRUCTURES	DN408	1		2,760.06	2,760.06
			STRUCTURES		

Thank you for the opportunity to estimate this project.

Total



Estimate

Date	Estimate #	
2/21/2025	229099	

Name / Address	
CITY OF DUNWOODY 4800 ASHFORD DUNWOODY DUNWOODY, GA 30338	

Project

1421 MOCKWELL CT

Item	Qty	Description	Rate	Amount
DN409	1	REMOVAL OF EXISTING DRAINAGE STRUCTURES	2,484.06	2,484.06
DN410 DN411 DN412	50 54	REMOVE EXISTING PIPE, ALL TYPES & SIZES SAW CUT EXISTING PAVEMENTS STONE #57	93.84 5.52 99.36	3,753.60 276.00 5,365.44
MISC	1	10% CONTINGENCY	14,425.18	14,425.18
TI 1 C 41		<u> </u>		

Thank you for the opportunity to estimate this project.

Total

\$158,677.07